www.ti.com

SNAS352F - JANUARY 2007 - REVISED NOVEMBER 2009

# ADC08D1000QML High Performance, Low Power, Dual 8-Bit, 1 GSPS A/D Converter

Check for Samples: ADC08D1000QML, ADC08D1000WG-QV

## **FEATURES**

- Total Ionizing Dose 300 krad(Si)
- Single Event Latch-Up >120 MeV/mg/cm<sup>2</sup>
- Internal Sample-and-Hold
- Single +1.9V ±0.1V Operation
- **Choice of SDR or DDR Output Clocking**
- Interleave Mode for 2x Sampling Rate
- **Multiple ADC Synchronization Capability**
- **Guaranteed No Missing Codes**
- **Serial Interface for Extended Control**
- Fine Adjustment of Input Full-Scale Range and Offset
- **Duty Cycle Corrected Sample Clock**

### **KEY SPECIFICATIONS**

- **Resolution 8 Bits**
- Max Conversion Rate 1 GSPS (min)
- Bit Error Rate 10-18 (typ)
- **ENOB at 498 MHz Input 7.4 Bits (typ)**
- DNL ±0.15 LSB (typ)
- **Power Consumption** 
  - Operating 1.6 W (typ)
  - Power Down Mode 3.5 mW (typ)

### **APPLICATIONS**

- **Communication Satellites/Systems**
- **Direct RF Down Conversion**

## DESCRIPTION

The ADC08D1000 is a dual, low power, high performance CMOS analog-to-digital converter that digitizes signals to 8 bits resolution at sampling rates up to 1.2 GSPS. Consuming a typical 1.6 Watts at 1 GSPS from a single 1.9 Volt supply, this device is guaranteed to have no missing codes over the full operating temperature range. The unique folding and interpolating architecture, the fully differential comparator design, the innovative design of the internal sample-and-hold amplifier and the selfcalibration scheme enable a very flat response of all dynamic parameters beyond Nyquist, producing a high 7.4 Effective Number Of Bits (ENOB) with a 498 MHz input signal and a 1 GHz sample rate while providing a 10<sup>-18</sup> Bit Error Rate (B.E.R.). Output formatting is offset binary and the Low Voltage Differential Signaling (LVDS) digital outputs are compliant with IEEE 1596.3-1996, with the exception of an adjustable common mode voltage between 0.8V and 1.13V.

Each converter has a 1:2 demultiplexer that feeds two LVDS buses and reduces the output data rate on each bus to half the sampling rate. The two converters can be interleaved and used as a single 2 GSPS ADC.


The converter typically consumes less than 3.5 mW in the Power Down Mode and is available in a 128lead, thermally enhanced multi-layer ceramic quad package and operates over the Military (-55°C ≤ T<sub>A</sub> ≤ +125°C) temperature range.

This part will work in a radiation environment, with excellent results, provided the guidelines in APPLICATIONS IN RADIATION ENVIRONMENTS are followed.

Please be aware that an important notice concerning availability, standard warranty, and use in critical applications of Texas Instruments semiconductor products and disclaimers thereto appears at the end of this data sheet. All trademarks are the property of their respective owners.




# **Block Diagram**





# **Pin Configuration**



<sup>\*</sup> Bottom of package must be soldered to ground plane to ensure rated performance.

## Figure 1. CFP Package See Package Number NBC0128A

#### Pin Descriptions and Equivalent Circuits

Pin Functions						
Pin No.	Symbol	Equivalent Circuit	Description			
3	OutV / SCLK	VA 50k GND	Output Voltage Amplitude and Serial Interface Clock. Tie this pin high for normal differential DCLK and data amplitude. Ground this pin for a reduced differential output amplitude and reduced power consumption. See The LVDS Outputs. When the extended control mode is enabled, this pin functions as the SCLK input which clocks in the serial data. See NORMAL/EXTENDED CONTROL for details on the extended control mode. See THE SERIAL INTERFACE for description of the serial interface.			



Pin Function	Pin Functions						
Pin No.	Symbol	Equivalent Circuit	Description				
4	OutEdge / DDR / SDATA	The state of the s	DCLK Edge Select, Double Data Rate Enable and Serial Data Input. This input sets the output edge of DCLK+ at which the output data transitions. (See OutEdge Setting). When this pin is floating or connected to 1/2 the supply voltage, DDR clocking is enabled. When the extended control mode is enabled, this pin functions as the SDATA input. See NORMAL/EXTENDED CONTROL for details on the extended control mode. See THE SERIAL INTERFACE for description of the serial interface.				
15	DCLK_RST	V <sub>A</sub>	DCLK Reset. A positive pulse on this pin is used to reset and synchronize the DCLK outs of multiple converters. See MULTIPLE ADC SYNCHRONIZATION for detailed description.				
26 29	PD PDQ		Power Down Pins. A logic high on the PD pin puts the entire device into the Power Down Mode. A logic high on the PDQ pin puts only the "Q" ADC into the Power Down mode.				
30	CAL	GND	Calibration Cycle Initiate. A minimum 640 input clock cycles logic low followed by a minimum of 640 input clock cycles high on this pin initiates the self calibration sequence. See Self Calibration for an overview of self-calibration and On-Command Calibration for a description of on-command calibration. See APPLICATIONS IN RADIATION ENVIRONMENTS for use in Radiation Environments.				
14	FSR/ECE		Full Scale Range Select and Extended Control Enable. In non-extended control mode, a logic low on this pin sets the full-scale differential input range to 650 mV <sub>P-P</sub> . A logic high on this pin sets the full-scale differential input range to 870 mV <sub>P-P</sub> . See The Analog Inputs. To enable the extended control mode, whereby the serial interface and control registers are employed, allow this pin to float or connect it to a voltage equal to V <sub>A</sub> /2. See NORMAL/EXTENDED CONTROL for information on the extended control mode. See APPLICATIONS IN RADIATION ENVIRONMENTS for use in Radiation Environments.				



Pin Functions						
Pin No.	Symbol	Equivalent Circuit	Description			
127	CalDly / DES / SCS	VA 50k 50k	Calibration Delay, Dual Edge Sampling and Serial Interface Chip Select. With a logic high or low on pin 14, this pin functions as Calibration Delay and sets the number of input clock cycles after power up before calibration begins (See Self-Calibration). With pin 14 floating, this pin acts as the enable pin for the serial interface input and the CalDly value becomes "0" (short delay with no provision for a long power-up calibration delay). When this pin is floating or connected to a voltage equal to $V_A/2$ , DES (Dual Edge Sampling) mode is selected where the "I" input is sampled at twice the input clock rate and the "Q" input is ignored. See Dual-Edge Sampling. See APPLICATIONS IN RADIATION ENVIRONMENTS for use in Radiation Environments.			
18 19	CLK+ CLK-	8 AGND SOK VBIAS	LVDS Clock input pins for the ADC. The differential clock signal must be a.c. coupled to these pins. The input signal is sampled on the falling edge of CLK+. See Acquiring the Input for a description of acquiring the input and THE CLOCK INPUTS for an overview of the clock inputs.			
11 10 22 23	V <sub>IN</sub> I+ V <sub>IN</sub> I- V <sub>IN</sub> Q+ V <sub>IN</sub> Q-	VA AGND VCMO 100 Control from VCMO	Analog signal inputs to the ADC. The differential full-scale input range is 650 mV $_{\text{P-P}}$ when the FSR pin is low, or 870 mV $_{\text{P-P}}$ when the FSR pin is high.			
7	V <sub>СМО</sub>	Vocation of the state of the st	Common Mode Voltage. The voltage output at this pin is required to be the common mode input voltage at $V_{IN}$ + and $V_{IN}$ – when d.c. coupling is used. This pin should be grounded when a.c. coupling is used at the analog inputs. This pin is capable of sourcing or sinking 100 $\mu$ A. See THE ANALOG INPUT.			




Pin Function			
Pin No.	Symbol	Equivalent Circuit	Description
31	$V_{BG}$	VA	Bandgap output voltage capable of 100 μA source/sink.
126	CalRun	GND	Calibration Running indication. This pin is at a logic high when calibration is running.
32	R <sub>EXT</sub>	V <sub>A</sub> GND	External bias resistor connection. Nominal value is 3.3k-Ohms (±0.1%) to ground. See Self-Calibration.
34 35	Tdiode_P Tdiode_N	Tdiode_P O	Temperature Diode Positive (Anode) and Negative (Cathode) for die temperature measurements. See Thermal Management.
83 / 78 84 / 77 85 / 76 86 / 75 89 / 72 90 / 71 91 / 70 92 / 69 93 / 68 94 / 67 95 / 66 96 / 65 100 / 61 101 / 60 102 / 59 103 / 58	DI7- / DQ7- DI7+ / DQ7+ DI6- / DQ6- DI6+ / DQ6+ DI5- / DQ5- DI5+ / DQ5+ DI4- / DQ4- DI4+ / DQ4+ DI3- / DQ3- DI3+ / DQ3+ DI2- / DQ2- DI2+ / DQ2- DI1- / DQ1- DI1+ / DQ1+ DI0- / DQ0- DI0+ / DQ0+	V <sub>DR</sub> V <sub>DR</sub> DR GND	I and Q channel LVDS Data Outputs that are not delayed in the output demultiplexer. Compared with the DId and DQd outputs, these outputs represent the later time samples. These outputs should always be terminated with a $100\Omega$ differential resistor.



Pin Functions					
Pin No.	Symbol	Equivalent Circuit	Description		
104 / 57 105 / 56 106 / 55 107 / 54 111 / 50 112 / 49 113 / 48 114 / 47 115 / 46 116 / 45 117 / 44 118 / 43 122 / 39 123 / 38 124 / 37 125 / 36	DId7- / DQd7- DId7+ / DQd7+ DId6- / DQd6- DId6+ / DQd6- DId5- / DQd5- DId5+ / DQd5- DId4- / DQd4- DId4- / DQd3- DId3- / DQd3- DId3+ / DQd3+ DId2- / DQd2- DId2+ / DQd1- DId1- / DQd1- DId1+ / DQd1+ DId0- / DQd0- DId0+ / DQd0-	DR GND	I and Q channel LVDS Data Outputs that are delayed by one CLK cycle in the output demultiplexer. Compared with the DI/DQ outputs, these outputs represent the earlier time sample. These outputs should always be terminated with a $100\Omega$ differential resistor.		
79 80	OR+ OR-	V <sub>DR</sub>	Out Of Range output. A differential high at these pins indicates that the differential input is out of range (outside the range ±325 mV or ±435 mV as defined by the FSR pin).		
82 81	DCLK+ DCLK-	DR GND	Differential Clock outputs used to latch the output data. Delayed and non-delayed data outputs are supplied synchronous to this signal. This signal is at 1/2 the input clock rate in SDR mode and at 1/4 the input clock rate in the DDR mode. DCLK outputs are not active during a calibration cycle.		
2, 5, 8, 13, 16, 17, 20, 25, 28, 33, 128	V <sub>A</sub>		Analog power supply pins. Bypass these pins to ground.		
40, 51 ,62, 73, 88, 99, 110, 121	$V_{DR}$		Output Driver power supply pins. Bypass these pins to DR GND.		
1, 6, 9, 12, 21, 24, 27, 41	GND		Ground return for V <sub>A</sub> .		
42, 53, 64, 74, 87, 97, 108, 119	DR GND		Ground return for V <sub>DR</sub> .		
52, 63, 98, 109, 120	NC		No Connection. Make no connection to these pins.		



These devices have limited built-in ESD protection. The leads should be shorted together or the device placed in conductive foam during storage or handling to prevent electrostatic damage to the MOS gates.





# Absolute Maximum Ratings (1)(2)

Supply Voltage (V <sub>A</sub> , V <sub>DR</sub> )		2.2V
Voltage on Any Input Pin		-0.15V to (V <sub>A</sub> +0.15V)
Voltage on V <sub>IN</sub> <sup>+</sup> , V <sub>IN</sub> <sup>-</sup>	(Maintaining Common Mode)	-0.15V to 2.5V
Ground Difference	GND - DR GND	0V to 100 mV
Input Current at Any Pin (3)		±25 mA
Package Input Current <sup>(3)</sup>		±50 mA
ESD Susceptibility (4)	Human Body Model	Class 3A (6000V)
Soldering Temperature, Infrared	10 seconds	235°C
Storage Temperature		−65°C to +175°C

- (1) All voltages are measured with respect to GND = DR GND = 0V, unless otherwise specified.
- (2) Absolute Maximum Ratings indicate limits beyond which damage to the device may occur. There is no guarantee of operation at the Absolute Maximum Ratings. Operating Ratings indicate conditions for which the device is functional, but do not guarantee specific performance limits. For guaranteed specifications and test conditions, see the Electrical Characteristics. The guaranteed specifications apply only for the test conditions listed. Some performance characteristics may degrade when the device is not operated under the listed test conditions.
- (3) When the input voltage at any pin exceeds the power supply limits (that is, less than GND or greater than V<sub>A</sub>), the current at that pin should be limited to 25 mA. The 50 mA maximum package input current rating limits the number of pins that can safely exceed the power supplies with an input current of 25 mA to two. This limit is not placed upon the power, ground and digital output pins.
- (4) Human body model is 100 pF capacitor discharged through a 1.5 k $\Omega$  resistor.

# Operating Ratings<sup>(1)(2)</sup>

Ambient Temperature Range	-55°C ≤ T <sub>A</sub> ≤ +125°C
Supply Voltage (V <sub>A</sub> )	+1.8V to +2.0V
Driver Supply Voltage (V <sub>DR</sub> )	+1.8V to V <sub>A</sub>
Analog Input Common Mode Voltage	V <sub>CMO</sub> ±50mV
V <sub>IN</sub> +, V <sub>IN</sub> - Voltage Range (Maintaining Common Mode)	0V to 2.15V (100% duty cycle) 0V to 2.5V (10% duty cycle)
Ground Difference ( GND - DR GND )	0V
CLK Pins Voltage Range	0V to V <sub>A</sub>
Differential CLK Amplitude	0.4V <sub>P-P</sub> to 2.0V <sub>P-P</sub>
Maximum Junction Temperature	150°C

- (1) Absolute Maximum Ratings indicate limits beyond which damage to the device may occur. There is no guarantee of operation at the Absolute Maximum Ratings. Operating Ratings indicate conditions for which the device is functional, but do not guarantee specific performance limits. For guaranteed specifications and test conditions, see the Electrical Characteristics. The guaranteed specifications apply only for the test conditions listed. Some performance characteristics may degrade when the device is not operated under the listed test conditions.
- (2) All voltages are measured with respect to GND = DR GND = 0V, unless otherwise specified.

### **Package Thermal Resistance**

Package θ <sub>JA</sub>		θ <sub>JC</sub> (Top of Package)	θ <sub>J-PAD (Thermal Pad)</sub>		
128L Cer Quad Gullwing	11.5°C/W	3.8°C/W	2.0°C/W		

# **Quality Conformance Inspection**

MIL-STD-883, Method 5005 - Group A

Subgroup	Description	Temp (°C)
1	Static tests at	+25
2	Static tests at	+125
3	Static tests at	-55
4	Dynamic tests at	+25
5	Dynamic tests at	+125

Submit Documentation Feedback

www.ti.com


SNAS352F - JANUARY 2007 - REVISED NOVEMBER 2009

Subgroup	Description	Temp (°C)
6	Dynamic tests at	-55
7	Functional tests at	+25
8A	Functional tests at	+125
8B	Functional tests at	-55
9	Switching tests at	+25
10	Switching tests at	+125
11	Switching tests at	-55
12	Setting time at	+25
13	Setting time at	+125
14	Setting time at	-55


### ADC08D1000 Converter Electrical Characteristics DC Parameters

The following specifications apply after calibration for  $V_A = V_{DR} = +1.9V_{DC}$ , OutV = 1.9V,  $V_{IN}$  FSR (a.c. coupled) = differential 870mV<sub>P-P</sub>,  $C_L = 10$  pF, Differential, a.c. coupled Sinewave Input Clock,  $f_{CLK} = 1$  GHz at 0.5V<sub>P-P</sub> with 50% duty cycle,  $V_{BG} = 1000$  Floating, Non-Extended Control Mode, SDR Mode,  $R_{EXT} = 3300\Omega \pm 0.1\%$ , Analog Signal Source Impedance =  $100\Omega$  Differential. **Boldface limits apply for T**<sub>A</sub> = **T**<sub>MIN</sub> to **T**<sub>MAX</sub><sup>(1)(2)</sup>

	Parameter	Test Conditions	Notes	Typ <sup>(3)</sup>	Min	Max	Units	Sub- groups
STATIC	CONVERTER CHARACTERIS	STICS						
INL	Integral Non-Linearity (Best fit)	DC Coupled, 1MHz Sine Wave Overanged		±0.3		±0.9	LSB	1, 2, 3
DNL	Differential Non-Linearity	DC Coupled, 1MHz Sine Wave Overanged		±0.15		±0.6	LSB	1, 2, 3
	Resolution with No Missing Codes					8	Bits	1, 2, 3
V <sub>OFF</sub>	Offset Error			-0.45	-1.5	0.5	LSB	1, 2, 3
PFSE	Positive Full-Scale Error		See <sup>(4)</sup>	-0.6		±27	mV	1, 2, 3
NFSE	Negative Full-Scale Error		See <sup>(4)</sup>	-1.31		±27	mV	1, 2, 3
	Out of Range Output Code	$(V_{IN}+) - (V_{IN}-) > + Full Scale$				255		1, 2, 3
	(In addition to OR Output high)	$(V_{IN}+) - (V_{IN}-) < -$ Full Scale				0		1, 2, 3
ANALO	G INPUT AND REFERENCE C	CHARACTERISTICS						
V <sub>IN</sub>	Full Scale Analog Differential Input Range	FSR pin 14 High		870	790	950	$mV_{P-P}$	1, 2, 3
R <sub>IN</sub>	Differential Input Resistance			100	94	106	Ω	1, 2, 3
ANALO	G OUTPUT CHARACTERISTI	cs						•



- (2) To guarantee accuracy, it is required that  $V_A$  and  $V_{DR}$  be well bypassed. Each supply pin must be decoupled with separate bypass capacitors. Additionally, achieving rated performance requires that the bottom be well grounded.
- (3) Typical figures are at  $T_A = 25$ °C, and represent most likely parametric norms.
- (4) Calculation of Full-Scale Error for this device assumes that the actual reference voltage is exactly its nominal value. Full-Scale Error for this device, therefore, is a combination of Full-Scale Error and Reference Voltage Error. See Figure 3. For relationship between Gain Error and Full-Scale Error, see Specification Definitions for Gain Error.





# ADC08D1000 Converter Electrical Characteristics DC Parameters (continued)

The following specifications apply after calibration for  $V_A = V_{DR} = +1.9 V_{DC}$ , OutV = 1.9V,  $V_{IN}$  FSR (a.c. coupled) = differential 870mV<sub>P-P</sub>,  $C_L = 10$  pF, Differential, a.c. coupled Sinewave Input Clock,  $f_{CLK} = 1$  GHz at 0.5V<sub>P-P</sub> with 50% duty cycle,  $V_{BG} = 1000$  Floating, Non-Extended Control Mode, SDR Mode,  $R_{EXT} = 33000 \pm 0.1\%$ , Analog Signal Source Impedance = 1000 Differential. **Boldface limits apply for T**<sub>A</sub> = **T**<sub>MIN</sub> to **T**<sub>MAX</sub><sup>(1)(2)</sup>

	Parameter	Test Conditions	Notes	Тур <sup>(3)</sup>	Min	Max	Units	Sub- groups
V <sub>CMO</sub>	Common Mode Output Voltage			1.26	0.95	1.45	V	1, 2, 3
$V_{BG}$	Bandgap Reference Output Voltage	I <sub>BG</sub> = ±100 μA		1.26	1.20	1.33	V	1, 2, 3
CLOCK	INPUT CHARACTERISTICS							•
V	Differential Clock Input	Sine Wave Clock		0.6	0.5	2.0	V <sub>P-P</sub>	1, 2, 3
$V_{ID}$	Level	Square Wave Clock		0.6	0.5	2.0	$V_{P-P}$	1, 2, 3
DIGITA	L CONTROL PIN CHARACTE	RISTICS						
$V_{IH}$	Logic High Input Voltage				.85xV <sub>A</sub>		V	1, 2, 3
V <sub>IL</sub>	Logic Low Input Voltage					.15xV A	V	1, 2, 3
DIGITA	L OUTPUT CHARACTERISTIC	cs						
M	LVDS Differential Output	Measured differentially, OutV = V <sub>A</sub> , V <sub>BG</sub> = Floating	See <sup>(5)</sup>	710	400	920	$mV_{P-P}$	1, 2, 3
V <sub>OD</sub>	Voltage	Measured differentially, OutV = GND, V <sub>BG</sub> = Floating	See <sup>(5)</sup>	510	280	720	$mV_{P-P}$	1, 2, 3
POWE	R SUPPLY CHARACTERISTIC	s			•			
I <sub>A</sub>	Analog Supply Current	PD = PDQ = Low PD = Low, PDQ = High PD = PDQ = High		660 430 1.8		765 508	mA mA mA	1, 2, 3 1, 2, 3
I <sub>DR</sub>	Output Driver Supply Current	PD = PDQ = Low PD = Low, PDQ = High PD = PDQ = High		200 112 0.012		275 157	mA mA mA	1, 2, 3 1, 2, 3
P <sub>D</sub>	Power Consumption	PD = PDQ = Low PD = Low, PDQ = High PD = PDQ = High		1.6 1.0 3.5		1.97 1.27	W W mW	1, 2, 3 1, 2, 3


<sup>(5)</sup> Tying  $V_{BG}$  to the supply rail will increase the output offset voltage ( $V_{OS}$ ) by 330mv (typical), as shown in the  $V_{OS}$  specification above. Tying  $V_{BG}$  to the supply rail will also affect the differential LVDS output voltage ( $V_{OD}$ ), causing it to increase by 40mV (typical).



### **ADC08D1000 Converter Electrical Characteristics AC Parameters**

The following specifications apply after calibration for  $V_A = V_{DR} = +1.9 V_{DC}$ , OutV = 1.9V,  $V_{IN}$  FSR (a.c. coupled) = differential 870mV<sub>P-P</sub>,  $C_L = 10$  pF, Differential, a.c. coupled Sinewave Input Clock,  $f_{CLK} = 1$  GHz at 0.5V<sub>P-P</sub> with 50% duty cycle,  $V_{BG} = 1000$  Floating, Non-Extended Control Mode, SDR Mode,  $R_{EXT} = 33000 \pm 0.1\%$ , Analog Signal Source Impedance = 1000 Differential. **Boldface limits apply for T**<sub>A</sub> = **T**<sub>MIN</sub> to **T**<sub>MAX</sub><sup>(1)(2)</sup>

Parameter		Test Conditions	Notes	Typ <sup>(3)</sup>	Min	Max	Units	Sub - groups
NORMA	L MODE (Non DES) DYNAM	IIC CONVERTER CHARACTERISTICS						
, , , , , , , , , , , , , , , , , , , ,		f <sub>IN</sub> = 100 MHz, V <sub>IN</sub> = FSR - 0.5 dB		7.5			Bits	
ENOB	Effective Number of Bits	f <sub>IN</sub> = 248 MHz, V <sub>IN</sub> = FSR - 0.5 dB		7.4	7.0		Bits	4, 5, 6
		$f_{IN} = 498 \text{ MHz}, V_{IN} = \text{FSR} - 0.5 \text{ dB}$		7.4	7.0		Bits	4, 5, 6
		$f_{IN} = 100 \text{ MHz}, V_{IN} = \text{FSR} - 0.5 \text{ dB}$		47			dB	
SINAD	Signal-to-Noise Plus Distortion Ratio	f <sub>IN</sub> = 248 MHz, V <sub>IN</sub> = FSR - 0.5 dB		46.3	43.9		dB	4, 5, 6
	Distortion (Valio	f <sub>IN</sub> = 498 MHz, V <sub>IN</sub> = FSR - 0.5 dB		46.3	43.9		dB	4, 5, 6
		f <sub>IN</sub> = 100 MHz, V <sub>IN</sub> = FSR - 0.5 dB		48			dB	
SNR	Signal-to-Noise Ratio	f <sub>IN</sub> = 248 MHz, V <sub>IN</sub> = FSR - 0.5 dB		47.1	44		dB	4, 5, 6
		$f_{IN} = 498 \text{ MHz}, V_{IN} = \text{FSR} - 0.5 \text{ dB}$		47.1	44		dB	4, 5, 6
		f <sub>IN</sub> = 100 MHz, V <sub>IN</sub> = FSR - 0.5 dB		-55			dB	
THD	Total Harmonic Distortion	f <sub>IN</sub> = 248 MHz, V <sub>IN</sub> = FSR - 0.5 dB		-55		-47. 5	dB	4, 5, 6
		f <sub>IN</sub> = 498 MHz, V <sub>IN</sub> = FSR - 0.5 dB		-55		-47. 5	dB	4, 5, 6
	Spurious Free Dynamic	f <sub>IN</sub> = 248 MHz, V <sub>IN</sub> = FSR - 0.5 dB		57			dB	
SFDR	Range	f <sub>IN</sub> = 498 MHz, V <sub>IN</sub> = FSR - 0.5 dB		57	47		dB	4, 5, 6
CLK1	Maximum Input Clock Frequency	Normal Mode (non DES)		1.2	1.0		GHz	4, 5, 6
NTERL	EAVE MODE (DES Pin 127=	Float) - DYNAMIC CONVERTER CHAR	ACTERIST	ICS		-		
=		f <sub>IN</sub> = 248 MHz, V <sub>IN</sub> = FSR - 0.5 dB		7.3			Bits	
ENOB	Effective Number of Bits	$f_{IN} = 498 \text{ MHz}, V_{IN} = FSR - 0.5 \text{ dB}$		7.3	6.8		Bits	4, 5, 6
01114.5	Signal to Noise Plus	f <sub>IN</sub> = 248 MHz, V <sub>IN</sub> = FSR - 0.5 dB		46			dB	
SINAD	Distortion Ratio	$f_{IN} = 498 \text{ MHz}, V_{IN} = FSR - 0.5 \text{ dB}$		46	42.5		dB	4, 5, 6
CNID	Cinnal to Naisa Dati-	f <sub>IN</sub> = 248 MHz, V <sub>IN</sub> = FSR - 0.5 dB		46.4			dB	
SNR	Signal to Noise Ratio	f <sub>IN</sub> = 498 MHz, V <sub>IN</sub> = FSR - 0.5 dB		46.4	43		dB	4, 5, 6
TUD.	Total Hammania Distantian	f <sub>IN</sub> = 248 MHz, V <sub>IN</sub> = FSR - 0.5 dB		-58			dB	
THD	Total Harmonic Distortion	$f_{IN} = 498 \text{ MHz}, V_{IN} = \text{FSR} - 0.5 \text{ dB}$		-58		-49	dB	4, 5, 6
CEDD	Spurious Free Dynamic	f <sub>IN</sub> = 248 MHz, V <sub>IN</sub> = FSR - 0.5 dB		57			dB	
SFDR	Range	f <sub>IN</sub> = 498 MHz, V <sub>IN</sub> = FSR - 0.5 dB		57	47		dB	4, 5, 6




- (2) To guarantee accuracy, it is required that  $V_A$  and  $V_{DR}$  be well bypassed. Each supply pin must be decoupled with separate bypass capacitors. Additionally, achieving rated performance requires that the bottom be well grounded.
- (3) Typical figures are at  $T_A = 25$ °C, and represent most likely parametric norms.



# **ADC08D1000 Converter Electrical Characteristics AC Timing Parameters**

The following specifications apply after calibration for  $V_A = V_{DR} = +1.9V_{DC}$ , OutV = 1.9V,  $V_{IN}$  FSR (a.c. coupled) = differential 870mV<sub>P-P</sub>,  $C_L = 10$  pF, Differential, a.c. coupled Sinewave Input Clock,  $f_{CLK} = 1$  GHz at 0.5V<sub>P-P</sub> with 50% duty cycle,  $V_{BG} = 1000$  Floating, Non-Extended Control Mode, SDR Mode,  $R_{EXT} = 33000 \pm 0.1\%$ , Analog Signal Source Impedance = 10000 Differential. **Boldface limits apply for T**<sub>A</sub> = T<sub>MIN</sub> to T<sub>MAX</sub> (1)(2)

Parameters		Test Conditions	Notes	Typ <sup>(3)</sup>	Min	Max	Units	Sub - groups
AC TIM	ING PARAMETERS				•			
t <sub>RPW</sub>	Reset Pulse Width				4		Clock Cycles	9, 10, 11
	Serial Clock Low Time				4		ns	9, 10, 11
	Serial Clock High Time				4		ns	9, 10, 11
t <sub>CAL_L</sub>	CAL Pin Low Time	See Figure 10			640		Clock Cycles	9, 10, 11
t <sub>CAL_H</sub>	CAL Pin High Time	See Figure 10			640		Clock Cycles	9, 10, 11




- (2) To guarantee accuracy, it is required that V<sub>A</sub> and V<sub>DR</sub> be well bypassed. Each supply pin must be decoupled with separate bypass capacitors. Additionally, achieving rated performance requires that the bottom be well grounded.
- (3) Typical figures are at  $T_A = 25$ °C, and represent most likely parametric norms.



### **Typical Electrical Characteristics**

**DC Parameters.** The following specifications apply after calibration for  $V_A = V_{DR} = +1.9V_{DC}$ , OutV = 1.9V,  $V_{IN}$  FSR (a.c. coupled) = differential 870mV<sub>P-P</sub>,  $C_L = 10$  pF, Differential, a.c. coupled Sinewave Input Clock,  $f_{CLK} = 1$  GHz at 0.5V<sub>P-P</sub> with 50% duty cycle,  $V_{BG} = Floating$ , Non-Extended Control Mode, SDR Mode,  $R_{EXT} = 3300\Omega \pm 0.1\%$ , Analog Signal Source Impedance =  $100\Omega$  Differential. (1)(2)

Parameters		Test Conditions Notes		Typ <sup>(3)</sup>	Units
STATIC CO	NVERTER CHARACTERISTICS				
V <sub>OFF</sub> _ADJ	Input Offset Adjustment Range	Extended Control Mode		±45	mV
FS_ADJ	Full-Scale Adjustment Range	Extended Control Mode		±20	% FS
NORMAL M	ODE (Non DES) DYNAMIC CONVERTE	R CHARACTERISTICS			
FPBW	Full Power Bandwidth	Normal Mode (non DES)		1.7	GHz
B.E.R.	Bit Error Rate			10 <sup>-18</sup>	Error/Sample
	Gain Flatness	d.c. to 498 MHz		±0.5	dBFS
	Gain Flathess	d.c. to 1 GHz		±1.0	dBFS
		$f_{IN} = 100 \text{ MHz}, V_{IN} = \text{FSR} - 0.5 \text{ dB}$		-60	dB
2nd Harm	Second Harmonic Distortion	$f_{IN} = 248 \text{ MHz}, V_{IN} = \text{FSR} - 0.5 \text{ dB}$		-60	dB
		f <sub>IN</sub> = 498 MHz, V <sub>IN</sub> = FSR - 0.5 dB		-60	dB
		$f_{IN}$ = 100 MHz, $V_{IN}$ = FSR - 0.5 dB		-65	dB
3rd Harm	Third Harmonic Distortion	f <sub>IN</sub> = 248 MHz, V <sub>IN</sub> = FSR - 0.5 dB		-65	dB
		f <sub>IN</sub> = 498 MHz, V <sub>IN</sub> = FSR - 0.5 dB		-65	dB
IMD	Intermodulation Distortion	$f_{IN1} = 321 \text{ MHz}, V_{IN} = FSR - 7 \text{ dB}$ $f_{IN2} = 326 \text{ MHz}, V_{IN} = FSR - 7 \text{ dB}$		-50	dB
INTERLEAV	/E MODE (DES Pin 127=Float) - Dynam	c Converter Characteristics			
FPBW (DES)	Full Power Bandwidth	Dual Edge Sampling Mode		900	MHz
0 111	0 111 : 5:	f <sub>IN</sub> = 248 MHz, V <sub>IN</sub> = FSR - 0.5 dB		-64	dB
2nd Harm	Second Harmonic Distortion	f <sub>IN</sub> = 498 MHz, V <sub>IN</sub> = FSR - 0.5 dB		-64	dB
3rd Harm	Third Harmonic Distortion	f <sub>IN</sub> = 248 MHz, V <sub>IN</sub> = FSR - 0.5 dB		-69	dB
		f <sub>IN</sub> = 498 MHz, V <sub>IN</sub> = FSR - 0.5 dB		-69	dB
ANALOG IN	IPUT AND REFERENCE CHARACTERIS	TICS	*		- <del>!</del>
V <sub>IN</sub>	Full Scale Analog Differential Input Range	FSR pin 14 Low		650	mVp-p mVp-p
V <sub>CMI</sub>	Analog Input Common Mode Voltage			V <sub>CMO</sub>	mV mV



- (2) To guarantee accuracy, it is required that V<sub>A</sub> and V<sub>DR</sub> be well bypassed. Each supply pin must be decoupled with separate bypass capacitors. Additionally, achieving rated performance requires that the bottom be well grounded.
- (3) Typical figures are at T<sub>A</sub> = 25°C, and represent most likely parametric norms.



# Typical Electrical Characteristics (continued)

**DC Parameters.** The following specifications apply after calibration for  $V_A = V_{DR} = +1.9V_{DC}$ , OutV = 1.9V,  $V_{IN}$  FSR (a.c. coupled) = differential 870mV<sub>P-P</sub>,  $C_L = 10$  pF, Differential, a.c. coupled Sinewave Input Clock,  $f_{CLK} = 1$  GHz at 0.5V<sub>P-P</sub> with 50% duty cycle,  $V_{BG} =$  Floating, Non-Extended Control Mode, SDR Mode,  $R_{EXT} = 3300\Omega \pm 0.1\%$ , Analog Signal Source Impedance =  $100\Omega$  Differential. (1)(2)

	Parameters	Test Conditions	Notes	Typ <sup>(3)</sup>	Units
	Analog Input Capacitance, Normal	Differential	See <sup>(4)</sup>	0.02	pF
CIN	operation	Each input pin to ground	See <sup>(4)</sup>	1.6	pF
	Analog Input Conscitones DEC Mada	Differential	See <sup>(4)</sup>	0.08	pF
	Analog Input Capacitance, DES Mode	Each input pin to ground	See <sup>(4)</sup>	2.2	pF
ANALOG OU	JTPUT CHARACTERISTICS				
V <sub>CMO_LVL</sub>	V <sub>CMO</sub> input threshold to set DC	V <sub>A</sub> = 1.8V		0.60	V
	Coupling mode	V <sub>A</sub> = 2.0V		0.66	V
TC V <sub>CMO</sub>	Common Mode Output Voltage Temperature Coefficient	$T_A = -55$ °C to +125°C		238	ppm/°C
$C_{LOAD} V_{CMO}$	Maximum V <sub>CMO</sub> load Capacitance			80	pF (max)
TC V <sub>BG</sub>	Bandgap Reference Voltage Temperature Coefficient	$T_A = -55$ °C to +125°C, $I_{BG} = \pm 100 \mu A$		61	ppm/°C
$C_{LOAD} V_{BG}$	Maximum Bandgap Reference Load Capacitance			80	pF (max)
TEMPERAT	URE DIODE CHARACTERISTICS		·		
<b>A</b> \/	Tomporatura Diada Valtaga	192 μA vs. 12 μA, Τ <sub>J</sub> = 25°C		71.23	mV
$\Delta V_{BE}$	Temperature Diode Voltage	192 μA vs. 12 μA, Τ <sub>J</sub> = 125°C		94.8	mV
CHANNEL-T	O-CHANNEL CHARACTERISTICS				
	Offset Match			1	LSB
	Positive Full-Scale Match	Zero offset selected in Control Register		1	LSB
	Negative Full-Scale Match	Zero offset selected in Control Register		1	LSB
	Phase Matching (I, Q)	F <sub>IN</sub> = 1.0 GHz		<1	Degree
X-TALK	Crosstalk from I (Agressor) to Q (Victim) Channel	Aggressor = 867 MHz F.S. Victim = 100 MHz F.S.		<del>-</del> 71	dB
X-TALK	Crosstalk from Q (Agressor) to I (Victim) Channel	Aggressor = 867 MHz F.S. Victim = 100 MHz F.S.		<del>-</del> 71	dB
CLOCK INP	UT CHARACTERISTICS	•	·		•
I <sub>I</sub>	Input Current	$V_{IN} = 0$ or $V_{IN} = V_A$		±1	μA
C <sub>IN</sub>	Input Capacitance	Differential	See <sup>(5)</sup>	0.02	pF
		Each input to ground	See <sup>(5)</sup>	1.5	pF
DIGITAL CO	NTROL PIN CHARACTERISTICS		1		<u> </u>
C <sub>IN</sub>	Input Capacitance	Each input to ground	See <sup>(6)</sup>	1.2	pF
	TPUT CHARACTERISTICS		1		<u> </u>
Δ V <sub>ODIFF</sub>	Change in LVDS Output Swing Between Logic Levels			±1	mV
V <sub>OS</sub>	Output Offset Voltage	V <sub>BG</sub> = Floating, See Figure 2		800	mV
V <sub>OS</sub>	Output Offset Voltage	V <sub>BG</sub> = V <sub>A</sub> , See Figure 2	See <sup>(7)</sup>	1130	mV
ΔV <sub>OS</sub>	Output Offset Voltage Change Between Logic Levels			±1	mV

<sup>(4)</sup> The analog and clock input capacitances are die capacitances only. Additional package capacitances of 0.65 pF differential and 0.95 pF each pin to ground are isolated from the die capacitances by lead and bond wire inductances.

<sup>(5)</sup> The analog and clock input capacitances are die capacitances only. Additional package capacitances of 0.65 pF differential and 0.95 pF each pin to ground are isolated from the die capacitances by lead and bond wire inductances.

<sup>(6)</sup> The digital control pin capacitances are die capacitances only. Additional package capacitance of 1.6 pF each pin to ground are isolated from the die capacitances by lead and bond wire inductances.

<sup>(7)</sup> Tying  $V_{BG}$  to the supply rail will increase the output offset voltage  $(V_{OS})$  by 330mv (typical), as shown in the  $V_{OS}$  specification above. Tying  $V_{BG}$  to the supply rail will also affect the differential LVDS output voltage  $(V_{OD})$ , causing it to increase by 40mV (typical).



### Typical Electrical Characteristics (continued)

**DC Parameters.** The following specifications apply after calibration for  $V_A = V_{DR} = +1.9V_{DC}$ , OutV = 1.9V,  $V_{IN}$  FSR (a.c. coupled) = differential 870mV<sub>P-P</sub>,  $C_L = 10$  pF, Differential, a.c. coupled Sinewave Input Clock,  $f_{CLK} = 1$  GHz at 0.5V<sub>P-P</sub> with 50% duty cycle,  $V_{BG} =$  Floating, Non-Extended Control Mode, SDR Mode,  $R_{EXT} = 3300\Omega \pm 0.1\%$ , Analog Signal Source Impedance =  $100\Omega$  Differential. (1)(2)


Parameters		Test Conditions	Notes	Typ <sup>(3)</sup>	Units
I <sub>OS</sub>	Output Short Circuit Current	Output+ & Output - connected to 0.8V		±4	mA
Z <sub>O</sub>	Differential Output Impedance			100	Ohms
V <sub>OH</sub>	CalRun H level output	I <sub>OH</sub> = -400uA	See <sup>(8)</sup>	1.65	V
V <sub>OL</sub>	CalRun L level output	I <sub>OH</sub> = -400uA	See <sup>(8)</sup>	0.15	V
POWER SU	PPLY CHARACTERISTICS				
PSRR1	D.C. Power Supply Rejection Ratio	Change in Full Scale Error with change in V <sub>A</sub> from 1.8V to 2.0V		30	dB
PSSR2	A.C. Power Supply Rejection Ratio	248 MHz, 50mV <sub>P-P</sub> riding on V <sub>A</sub>		51	dB

<sup>(8)</sup> This parameter is guaranteed by design and/or characterization and is not tested in production.

# Typical Electrical Characteristics (continued)

**AC Parameters.** The following specifications apply after calibration for  $V_A = V_{DR} = +1.9V_{DC}$ , OutV = 1.9V,  $V_{IN}$  FSR (a.c. coupled) = differential 870mV<sub>P-P</sub>,  $C_L = 10$  pF, Differential, a.c. coupled Sinewave Input Clock,  $f_{CLK} = 1$  GHz at 0.5V<sub>P-P</sub> with 50% duty cycle,  $V_{BG} = Floating$ , Non-Extended Control Mode, SDR Mode,  $R_{EXT} = 3300\Omega \pm 0.1\%$ , Analog Signal Source Impedance =  $100\Omega$  Differential. (1)(2)

Parameters		Parameters Test Conditions		Typ <sup>(3)</sup>	Units
f <sub>CLK1</sub>	Maximum Input Clock Frequency	DES Mode		1.0	GHz
f <sub>CLK2</sub>	Minimum Input Clock Frequency	Normal Mode (non DES)		200	MHz
f <sub>CLK2</sub>	Minimum Input Clock Frequency	DES Mode		500	MHz
	Input Clock Duty Cycle	200 MHz ≤ Input clock frequency ≤ 1 GHz (Normal Mode)		50	% (min) % (max)
	Input Clock Duty Cycle	500 MHz ≤ Input clock frequency ≤ 1 GHz <b>(DES Mode)</b>		50	% (min) % (max)
t <sub>CL</sub>	Input Clock Low Time			500	ps (min)
t <sub>CH</sub>	Input Clock High Time			500	ps (min)
	DCLK Duty Cycle			50	% (min) % (max)
t <sub>RS</sub>	Reset Setup Time			150	ps
t <sub>RH</sub>	Reset Hold Time			250	ps
	Syncronizing Edge to DCLK Output	f <sub>CLKIN</sub> = 1.0 GHz		3.53	ns
t <sub>SD</sub>	Delay	f <sub>CLKIN</sub> = 200 MHz		3.85	ns
t <sub>LHT</sub>	Differential Low to High Transition Time	10% to 90%, C <sub>L</sub> = 2.5 pF		250	ps
t <sub>HLT</sub>	Differential High to Low Transition Time	10% to 90%, C <sub>L</sub> = 2.5 pF		250	ps



- (2) To guarantee accuracy, it is required that  $V_A$  and  $V_{DR}$  be well bypassed. Each supply pin must be decoupled with separate bypass capacitors. Additionally, achieving rated performance requires that the bottom be well grounded.
- (3) Typical figures are at T<sub>A</sub> = 25°C, and represent most likely parametric norms.



# Typical Electrical Characteristics (continued) (continued)

**AC Parameters.** The following specifications apply after calibration for  $V_A = V_{DR} = +1.9V_{DC}$ , OutV = 1.9V,  $V_{IN}$  FSR (a.c. coupled) = differential 870mV<sub>P-P</sub>,  $C_L = 10$  pF, Differential, a.c. coupled Sinewave Input Clock,  $f_{CLK} = 1$  GHz at 0.5V<sub>P-P</sub> with 50% duty cycle,  $V_{BG} = Floating$ , Non-Extended Control Mode, SDR Mode,  $R_{EXT} = 3300\Omega \pm 0.1\%$ , Analog Signal Source Impedance =  $100\Omega$  Differential. (1)(2)

Parameters		Test Conditions	Notes	Typ <sup>(3)</sup>	Units
t <sub>OSK</sub>	DCLK to Data Output Skew	50% of DCLK transition to 50% of Data transition, SDR Mode and DDR Mode, 0° DCLK		±50	ps (max)
t <sub>SU</sub>	Data to DCLK Set-Up Time	DDR Mode, 90° DCLK		1	ns
t <sub>H</sub>	DCLK to Data Hold Time	DDR Mode, 90° DCLK		1	ns
t <sub>AD</sub>	Sampling (Aperture) Delay	Input CLK+ Fall to Acquisition of Data		1.3	ns
t <sub>AJ</sub>	Aperture Jitter			0.4	ps rms
t <sub>OD</sub>	Input Clock to Data Output Delay (in addition to Pipeline Delay)	50% of Input Clock transition to 50% of Data transition		3.1	ns
	Pipeline Delay (Latency)	DI Outputs	See <sup>(4)(5)</sup>	13	
		Dld Outputs		14	
		DQ Outputs Normal Mode		13	Input Clock
		DQ Outputs DES Mode		13.5	Cycles
		DQd Outputs Normal Mode		14	
		DQd Outputs Normal Mode		14.5	
	Over Range Recovery Time	Differential V <sub>IN</sub> step from ±1.2V to 0V to get accurate conversion		1	Input Clock Cycle
t <sub>WU</sub>	PD low to Rated Accuracy Conversion (Wake-Up Time)			500	ns
f <sub>SCLK</sub>	Serial Clock Frequency			100	MHz
t <sub>SSU</sub>	Data to Serial Clock Setup Time			2.5	ns (min)
t <sub>SH</sub>	Data to Serial Clock Hold Time			1	ns (min)
t <sub>CAL</sub>	Calibration Cycle Time			7.1x10 <sup>5</sup>	Clock Cycles
t <sub>CalDly</sub>	Calibration delay determined by pin 127 Low	See Self-Calibration, Figure 10	See <sup>(4)</sup>	2 <sup>25</sup>	Clock Cycles (min)
t <sub>CalDly</sub>	Calibration delay determined by pin 127 High	See Self-Calibration, Figure 10	See <sup>(4)</sup>	2 <sup>31</sup>	Clock Cycles (max)

<sup>(4)</sup> This parameter is guaranteed by design and is not tested in production.

<sup>(5)</sup> Each of the two converters of the ADC08D1000 has two LVDS output buses, which each clock data out at one half the sample rate. The data at each bus is clocked out at one half the sample rate. The second bus (D0 through D7) has a pipeline latency that is one Input Clock cycle less than the latency of the first bus (Dd0 through Dd7).



### **Specification Definitions**

**APERTURE (SAMPLING) DELAY** is that time required after the fall of the clock input for the sampling switch to open. The Sample/Hold circuit effectively stops capturing the input signal and goes into the "hold" mode the aperture delay time ( $t_{AD}$ ) after the input clock goes low.

**APERTURE JITTER**  $(t_{AJ})$  is the variation in aperture delay from sample to sample. Aperture jitter shows up as input noise.

**Bit Error Rate (B.E.R.)** is the probability of error and is defined as the probable number of errors per unit of time divided by the number of bits seen in that amount of time. A B.E.R. of 10<sup>-18</sup> corresponds to a statistical error in one bit about every four (4) years.

**CLOCK DUTY CYCLE** is the ratio of the time that the clock wave form is at a logic high to the total time of one clock period.

**DIFFERENTIAL NON-LINEARITY (DNL)** is the measure of the maximum deviation from the ideal step size of 1 LSB. Measured at 1 GSPS with a ramp input.

**EFFECTIVE NUMBER OF BITS (ENOB, or EFFECTIVE BITS)** is another method of specifying Signal-to-Noise and Distortion Ratio, or SINAD. ENOB is defined as (SINAD - 1.76) / 6.02 and says that the converter is equivalent to a perfect ADC of this (ENOB) number of bits.

**FULL POWER BANDWIDTH (FPBW)** is a measure of the frequency at which the reconstructed output fundamental drops 3 dB below its low frequency value for a full scale input.

**GAIN ERROR** is the deviation from the ideal slope of the transfer function. It can be calculated from Offset and Full-Scale Errors:

Positive Gain Error = Offset Error - Positive Full-Scale Error

Negative Gain Error = -(Offset Error - Negative Full-Scale Error)

Gain Error = Negative Full-Scale Error - Positive Full-Scale Error = Positive Gain Error + Negative Gain Error

**INTEGRAL NON-LINEARITY (INL)** is a measure of the deviation of each individual code from a straight line through the input to output transfer function. The deviation of any given code from this straight line is measured from the center of that code value. The best fit method is used.

**INTERMODULATION DISTORTION (IMD)** is the creation of additional spectral components as a result of two sinusoidal frequencies being applied to the ADC input at the same time. It is defined as the ratio of the power in the second and third order intermodulation products to the power in one of the original frequencies. IMD is usually expressed in dBFS.

LSB (LEAST SIGNIFICANT BIT) is the bit that has the smallest value or weight of all bits. This value is

$$V_{FS}/2^{n} \tag{1}$$

where  $V_{FS}$  is the differential full-scale amplitude of 650 mV or 870 mV as set by the FSR input and "n" is the ADC resolution in bits, which is 8 for the ADC08D1000.

**LVDS DIFFERENTIAL OUTPUT VOLTAGE (V\_{OD})** is the absolute value of the difference between the  $V_D$ + &  $V_D$ -outputs; each measured with respect to Ground.




Figure 2.

**LVDS OUTPUT OFFSET VOLTAGE (V<sub>os</sub>)** is the midpoint between the D+ and D- pins output voltage; ie.,  $[(V_D+)+(V_D-)]/2$ .

SNAS352F - JANUARY 2007-REVISED NOVEMBER 2009



www.ti.com

MISSING CODES are those output codes that are skipped and will never appear at the ADC outputs. These codes cannot be reached with any input value.

MSB (MOST SIGNIFICANT BIT) is the bit that has the largest value or weight. Its value is one half of full scale.

NEGATIVE FULL-SCALE ERROR (NFSE) is a measure of how far the last code transition is from the ideal 1/2 LSB above a differential -435 mV with the FSR pin high, or 1/2 LSB above a differential -325 mV with the FSR pin low. For the ADC08D1000 the reference voltage is assumed to be ideal, so this error is a combination of fullscale error and reference voltage error.

OFFSET ERROR (VOFF) is a measure of how far the mid-scale point is from the ideal zero voltage differential input.

Offset Error = Actual Input causing average of 8k samples to result in an average code of 127.5.

OUTPUT DELAY (top) is the time delay (in addition to Pipeline Delay) after the falling edge of DCLK before the data update is present at the output pins.

OVER-RANGE RECOVERY TIME is the time required after the differential input voltages goes from ±1.2V to 0V for the converter to recover and make a conversion with its rated accuracy.

PIPELINE DELAY (LATENCY) is the number of input clock cycles between initiation of conversion and when that data is presented to the output driver stage. New data is available at every clock cycle, but the data lags the conversion by the Pipeline Delay plus the t<sub>OD</sub>.

POSITIVE FULL-SCALE ERROR (PFSE) is a measure of how far the last code transition is from the ideal 1-1/2 LSB below a differential +435 mV with the FSR pin high, or 1-1/2 LSB below a differential +325 mV with the FSR pin low. For the ADC08D1000 the reference voltage is assumed to be ideal, so this error is a combination of fullscale error and reference voltage error.

POWER SUPPLY REJECTION RATIO (PSRR) can be one of two specifications. PSRR1 (DC PSRR) is the ratio of the change in full-scale error that results from a power supply voltage change from 1.8V to 2.0V. PSRR2 (AC PSRR) is a measure of how well an a.c. signal riding upon the power supply is rejected from the output and is measured with a 248 MHz, 50 mV<sub>P-P</sub> signal riding upon the power supply. It is the ratio of the output amplitude of that signal at the output to its amplitude on the power supply pin. PSRR is expressed in dB.

SIGNAL TO NOISE RATIO (SNR) is the ratio, expressed in dB, of the rms value of the input signal at the output to the rms value of the sum of all other spectral components below one-half the sampling frequency, not including harmonics or d.c.

SIGNAL TO NOISE PLUS DISTORTION (S/(N+D) or SINAD) is the ratio, expressed in dB, of the rms value of the input signal at the output to the rms value of all of the other spectral components below half the input clock frequency, including harmonics but excluding d.c.

SPURIOUS-FREE DYNAMIC RANGE (SFDR) is the difference, expressed in dB, between the rms values of the input signal at the output and the peak spurious signal, where a spurious signal is any signal present in the output spectrum that is not present at the input, excluding d.c.

TOTAL HARMONIC DISTORTION (THD) is the ratio expressed in dB, of the rms total of the first nine harmonic levels at the output to the level of the fundamental at the output. THD is calculated as

THD = 
$$20 \times \log \sqrt{\frac{A_{f2}^2 + \dots + A_{f10}^2}{A_{f1}^2}}$$
 (2)

where A<sub>f1</sub> is the RMS power of the fundamental (output) frequency and A<sub>f2</sub> through A<sub>f10</sub> are the RMS power of the first 9 harmonic frequencies in the output spectrum.

- Second Harmonic Distortion (2nd Harm) is the difference, expressed in dB, between the RMS power in the input frequency seen at the output and the power in its 2nd harmonic level at the output.
- Third Harmonic Distortion (3rd Harm) is the difference expressed in dB between the RMS power in the input frequency seen at the output and the power in its 3rd harmonic level at the output.



### **Transfer Characteristic**




Figure 3. Input / Output Transfer Characteristic

### **TEST CIRCUIT DIAGRAMS**

### **Timing Diagrams**




Figure 4. ADC08D1000 Timing — SDR Clocking






Figure 5. ADC08D1000 Timing — DDR Clocking




Figure 6. Serial Interface Timing




Figure 7. Clock Reset Timing in DDR Mode






Figure 8. Clock Reset Timing in SDR Mode with OUTEDGE Low




Figure 9. Clock Reset Timing in SDR Mode with OUTEDGE High




Figure 10. Self Calibration and On-Command Calibration Timing







Figure 11. For On-Command Calibration Only (See APPLICATIONS IN RADIATION ENVIRONMENTS, The Cal Pin)



# **Typical Performance Characteristics**

 $V_A = V_{DR} = 1.9V$ ,  $F_{CLK} = 1000MHz$ ,  $T_A = 25$ °C unless otherwise stated.









Figure 14.






Figure 13.




Figure 15.







Figure 17.





 $V_A = V_{DR} = 1.9V$ ,  $F_{CLK} = 1000 MHz$ ,  $T_A = 25$ °C unless otherwise stated.


















 $V_A = V_{DR} = 1.9V$ ,  $F_{CLK} = 1000 MHz$ ,  $T_A = 25^{\circ}C$  unless otherwise stated.






25 50


TEMPERATURE (°C)


Figure 26.


-60

-50














 $V_A = V_{DR} = 1.9V$ ,  $F_{CLK} = 1000MHz$ ,  $T_A = 25$ °C unless otherwise stated.







## Spectral Response at FIN = 248 MHZ







Figure 31.



Spectral Response at FIN = 498 MHZ







Figure 35.





 $V_A = V_{DR} = 1.9V$ ,  $F_{CLK} = 1000 MHz$ ,  $T_A = 25$ °C unless otherwise stated.













#### FUNCTIONAL DESCRIPTION

The ADC08D1000 is a versatile A/D Converter with an innovative architecture permitting very high speed operation. The controls available ease the application of the device to circuit solutions. Optimum performance requires adherence to the provisions discussed here and in the Applications Information Section.

While it is not recommended in radiation environments to allow an active pin to float, pins 4, 14 and 127 of the ADC08D1000 are designed to be left floating without jeopardy. In all discussions throughout this data sheet, whenever a function is called by allowing a control pin to float, connecting that pin to a potential of one half the  $V_A$  supply voltage will have the same effect as allowing it to float.

### **OVERVIEW**

The ADC08D1000 uses a calibrated folding and interpolating architecture that achieves over 7.4 effective bits. The use of folding amplifiers greatly reduces the number of comparators and power consumption. Interpolation reduces the number of front-end amplifiers required, minimizing the load on the input signal and further reducing power requirements. In addition to other things, on-chip calibration reduces the INL bow often seen with folding architectures. The result is an extremely fast, high performance, low power converter.

The analog input signal that is within the converter's input voltage range is digitized to eight bits at speeds of 200 MSPS to 1.3 GSPS, typical. Differential input voltages below negative full-scale will cause the output word to consist of all zeroes. Differential input voltages above positive full-scale will cause the output word to consist of all ones. Either of these conditions at either the "I" or "Q" input will cause the OR (Out of Range) output to be activated. This single OR output indicates when the output code from one or both of the channels is below negative full scale or above positive full scale.

Each of the two converters has a 1:2 demultiplexer that feeds two LVDS output buses. The data on these buses provide an output word rate on each bus at half the ADC sampling rate and must be interleaved by the user to provide output words at the full conversion rate.

The output levels may be selected to be normal or reduced. Using reduced levels saves power but could result in erroneous data capture of some or all of the bits, especially at higher sample rates and in marginally designed systems.

#### **Self-Calibration**

A self-calibration is performed upon power-up and can also be invoked by the user upon command. Calibration trims the  $100\Omega$  analog input differential termination resistor and minimizes full-scale error, offset error, DNL and INL, resulting in maximizing SNR, THD, SINAD (SNDR) and ENOB. Internal bias currents are also set with the calibration process. All of this is true whether the calibration is performed upon power up or is performed upon command. Running the self calibration is an important part of this chip's functionality and is required in order to obtain adequate performance. In addition to the requirement to be run at power-up, self calibration must be rerun whenever the sense of the FSR pin is changed. For best performance, we recommend that self calibration be run 20 seconds or more after application of power and whenever the operating temperature changes significantly, according to the system design performance specifications. See On-Command Calibration for more information. Calibration can not be initiated or run while the device is in the power-down mode. See Power Down for information on the interaction between Power Down and Calibration.

During the calibration process, the input termination resistor is trimmed to a value that is equal to  $R_{\text{EXT}}$  / 33. This external resistor is located between pin 32 and ground.  $R_{\text{EXT}}$  must be 3300  $\Omega$  ±0.1%. With this value, the input termination resistor is trimmed to be 100  $\Omega$ . Because  $R_{\text{EXT}}$  is also used to set the proper current for the Track and Hold amplifier, for the preamplifiers and for the comparators, other values of  $R_{\text{EXT}}$  should not be used.

In normal operation, calibration is performed just after application of power and whenever a valid calibration command is given, which is holding the CAL pin low for at least 640 input clock cycles, then hold it high for at least another 640 input clock cycles. The time taken by the calibration procedure is specified in the A.C. Characteristics Table. Holding the CAL pin high upon power up will prevent the calibration process from running until the CAL pin experiences the above-mentioned 640 input clock cycles low followed by 640 cycles high.



CalDly (pin 127) is used to select one of two delay times after the application of power to the start of calibration. This calibration delay is 2<sup>25</sup> input clock cycles (about 33.6 ms at 1 GSPS) with CalDly low, or 2<sup>31</sup> input clock cycles (about 2.15 seconds at 1 GSPS) with CalDly high. These delay values allow the power supply to come up and stabilize before calibration takes place. If the PD pin is high upon power-up, the calibration delay counter will be disabled until the PD pin is brought low. Therefore, holding the PD pin high during power up will further delay the start of the power-up calibration cycle. The best setting of the CalDly pin depends upon the power-on settling time of the power supply.

The CalRun output is high whenever the calibration procedure is running. This is true whether the calibration is done at power-up or on-command.

### **Acquiring the Input**

Data is acquired at the falling edge of CLK+ (pin 18) and the digital equivalent of that data is available at the digital outputs 13 input clock cycles later for the DI and DQ output buses and 14 input clock cycles later for the DId and DQd output buses. There is an additional internal delay called t<sub>OD</sub> before the data is available at the outputs. See Timing Diagrams. The ADC08D1000 will convert as long as the input clock signal is present. The fully differential comparator design and the innovative design of the sample-and-hold amplifier, together with self calibration, enables a very flat SINAD/ENOB response beyond 1.0 GHz. The ADC08D1000 output data signaling is LVDS and the output format is offset binary.

## **Control Modes**

Much of the user control can be accomplished with several control pins that are provided. Examples include initiation of the calibration cycle, power down mode and full scale range setting. However, the ADC08D1000 also provides an Extended Control mode whereby a serial interface is used to access register-based control of several advanced features. The Extended Control mode is not intended to be enabled and disabled dynamically. Rather, the user is expected to employ either the normal control mode or the Extended Control mode at all times. When the device is in the Extended Control mode, pin-based control of several features is replaced with register-based control and those pin-based controls are disabled. These pins are OutV (pin 3), OutEdge/DDR (pin 4), FSR (pin 14) and CalDly/DES (pin 127). See NORMAL/EXTENDED CONTROL for details on the Extended Control mode.

### The Analog Inputs

The ADC08D1000 must be driven with a differential input signal. Operation with a single-ended signal is not recommended. It is important that the input signals are either a.c. coupled to the inputs with the  $V_{CMO}$  pin grounded, or d.c. coupled with the  $V_{CMO}$  pin left floating. An input common mode voltage equal to the  $V_{CMO}$  output must be provided when d.c. coupling is used.

Two full-scale range settings are provided with pin 14 (FSR). A high on pin 14 causes an input full-scale range setting of 870 mV<sub>P-P</sub>, while grounding pin 14 causes an input full-scale range setting of 650 mV<sub>P-P</sub>. The full-scale range setting operates equally on both ADCs.

In the Extended Control mode, the full-scale input range can be set to values between 560 mV<sub>P-P</sub> and 840 mV<sub>P-P</sub> through a serial interface. See THE REFERENCE VOLTAGE

### Clocking

The ADC08D1000 must be driven with an a.c. coupled, differential clock signal. THE CLOCK INPUTS describes the use of the clock input pins. A differential LVDS output clock is available for use in latching the ADC output data into whatever device is used to receive the data.

The ADC08D1000 offers options for input and output clocking. These options include a choice of Dual Edge Sampling (DES) or "interleaved mode" where the ADC08D1000 performs as a single device converting at twice the input clock rate, a choice of which DCLK (DCLK) edge the output data transitions on, and a choice of Single Data Rate (SDR) or Double Data Rate (DDR) outputs.

The ADC08D1000 also has the option to use a duty cycle corrected clock receiver as part of the input clock circuit. This feature is enabled by default and provides improved ADC clocking especially in the Dual-Edge Sampling mode (DES). This circuitry allows the ADC to be clocked with a signal source having a duty cycle ratio of 80 / 20 % (worst case) for both the normal and the Dual Edge Sampling modes.



### **Dual-Edge Sampling**

The DES mode allows one of the ADC08D1000's inputs (I or Q Channel) to be sampled by both ADCs. One ADC samples the input on the positive edge of the input clock and the other ADC samples the same input on the other edge of the input clock. A single input is thus sampled twice per input clock cycle, resulting in an overall sample rate of twice the input clock frequency, or 2 GSPS with a 1 GHz input clock.

In this mode the outputs are interleaved such that the data is effectively demultiplexed 1:4. Since the sample rate is doubled, each of the 4 output buses have a 500 MSPS output rate with a 1 GHz input clock. All data is available in parallel. The four bytes of parallel data that are output with each clock is in the following sampling order, from the earliest to the latest: DQd, Dld, DQ, Dl. Table 1 indicates what the outputs represent for the various sampling possibilities.

In the non-extended mode of operation only the "I" input can be sampled in the DES mode. In the extended mode of operation the user can select which input is sampled.

The ADC08D1000 also includes an automatic clock phase background calibration feature which can be used in DES mode to automatically and continuously adjust the clock phase of the I and Q channel. This feature removes the need to adjust the clock phase setting manually and provides optimal Dual-Edge Sampling ENOB performance.

**IMPORTANT NOTE:** The background calibration feature in DES mode does not replace the requirement for On-Command Calibration which should be run before entering DES mode, or if a large swing in ambient temperature is experienced by the device.

DES Mode should not be used in radiation environments. See APPLICATIONS IN RADIATION ENVIRONMENTS.

**Dual-Edge Sampling Mode (DES)** Data Outputs (Always sourced **Normal Sampling Mode** with respect to fall of DCLK) **I-Channel Selected** Q-Channel Selected \* "I" Input Sampled with Fall of "I" Input Sampled with Fall of "Q" Input Sampled with Fall of DI CLK 13 cycles earlier. CLK 13 cycles earlier. CLK 13 cycles earlier. "I" Input Sampled with Fall of "I" Input Sampled with Fall of "Q" Input Sampled with Fall of Dld CLK 14 cycles earlier. CLK 14 cycles earlier. CLK 14 cycles earlier. "Q" Input Sampled with Fall of "I" Input Sampled with Rise of "Q" Input Sampled with Rise of DQ CLK 13.5 cycles earlier. CLK 13 cycles earlier. CLK 13.5 cycles earlier. "Q" Input Sampled with Fall of "I" Input Sampled with Rise of "Q" Input Sampled with Rise of DQd CLK 14 cycles after being CLK 14.5 cycles earlier. CLK 14.5 cycles earlier. sampled.

Table 1. Input Channel Samples Produced at Data Outputs

\* Note that, in the DES mode, the "Q" channel input can only be selected for sampling in the Extended Control Mode.

### **OutEdge Setting**

To help ease data capture in the SDR mode, the output data may be caused to transition on either the positive or the negative edge of the output data clock (DCLK). This is chosen with the OutEdge input (pin 4). A high on the OutEdge input pin causes the output data to transition on the rising edge of DCLK, while grounding this input causes the output to transition on the falling edge of DCLK. See Output Edge Synchronization.

### **Double Data Rate**

A choice of single data rate (SDR) or double data rate (DDR) output is offered. With single data rate the output clock (DCLK) frequency is the same as the data rate of the two output buses. With double data rate the DCLK frequency is half the data rate and data is sent to the outputs on both edges of DCLK. DDR clocking is enabled in non-Extended Control mode by allowing pin 4 to float.

Submit Documentation Feedback

www.ti.com

### The LVDS Outputs

The data outputs, the Out Of Range (OR) and DCLK, are LVDS. Output current sources provide 3 mA of output current to a differential 100 Ohm load when the OutV input (pin 14) is high or 2.2 mA when the OutV input is low. For short LVDS lines and low noise systems, satisfactory performance may be realized with the OutV input low, which results in lower power consumption. If the LVDS lines are long and/or the system in which the ADC08D1000 is used is noisy, it may be necessary to tie the OutV pin high.

The LVDS data output have a typical common mode voltage of 800mV when the  $V_{BG}$  pin is unconnected and floating. This common mode voltage can be increased to 1.13V by tying the  $V_{BG}$  pin to  $V_{A}$  if a higher common mode is required.

**IMPORTANT NOTE:** Tying the  $V_{BG}$  pin to  $V_{A}$  will also increase the differential LVDS output voltage by upto 40mV.

### **Power Down**

The ADC08D1000 is in the active state when the Power Down pin (PD) is low. When the PD pin is high, the device is in the power down mode. In this power down mode the data output pins (positive and negative) are put into a high impedance state and the devices power consumption is reduced to a minimal level. The DCLK+/- and OR +/- are not tri-stated, they are weakly pulled down to ground internally. Therefore when both I and Q are powered down the DCLK +/- and OR +/- should not be terminated to a DC voltage.

A high on the PDQ pin will power down the "Q" channel and leave the "I" channel active. There is no provision to power down the "I" channel independently of the "Q" channel. Upon return to normal operation, the pipeline will contain meaningless information.

If the PD input is brought high while a calibration is running, the device will not go into power down until the calibration sequence is complete. However, if power is applied and PD is already high, the device will not begin the calibration sequence until the PD input goes low. If a manual calibration is requested while the device is powered down, the calibration will not begin at all. That is, the manual calibration input is completely ignored in the power down state. Calibration will function with the "Q" channel powered down, but that channel will not be calibrated if PDQ is high. If the "Q" channel is subsequently to be used, it is necessary to perform a calibration after PDQ is brought low.

### NORMAL/EXTENDED CONTROL

The ADC08D1000 may be operated in one of two modes. In the simpler standard control mode, the user affects available configuration and control of the device through several control pins. The "extended control mode" provides additional configuration and control options through a serial interface and a set of 8 registers. The two control modes are selected with pin 14 (FSR/ECE: Extended Control Enable). The choice of control modes is required to be a fixed selection and is not intended to be switched dynamically while the device is operational.

Table 2 shows how several of the device features are affected by the control mode chosen. **See APPLICATIONS IN RADIATION ENVIRONMENTS** for use in Radiation Environments.

Table 2. Features and modes

Normal Control Mode

Feature	Normal Control Mode	Extended Control Mode
SDR or DDR Clocking	Selected with pin 4	Selected with DE bit in the Configuration Register
DDR Clock Phase	Not Selectable (0° Phase Only)	Selected with DCP bit in the Configuration Register. See REGISTER DESCRIPTION
SDR Data transitions with rising or falling DCLK edge	Selected with pin 4	Selected with the OE bit in the Configuration Register
LVDS output level	Selected with pin 3	Selected with the OV bit (9)in the Configuration Register
Power-On Calibration Delay	Delay Selected with pin 127	Short delay only.
Full-Scale Range	Options (650 mV <sub>P-P</sub> or 870 mV <sub>P-P</sub> ) selected with pin 14. Selected range applies to both channels.	Up to 512 step adjustments over a nominal range of 560 mV to 840 mV. Separate range selected for I- and Q-Channels. Selected using registers 3H and Bh

Copyright © 2007–2009, Texas Instruments Incorporated

Submit Documentation Feedback



#### Table 2. Features and modes (continued)

Feature	Normal Control Mode	Extended Control Mode
Input Offset Adjust	Not possible	Separate ±45 mV adjustments in 512 steps for each channel using registers 2h and Ah
Dual Edge Sampling Selection	Enabled with pin 127	Enabled through DES Enable Register
Dual Edge Sampling Input Channel Selection	Only I-Channel Input can be used	Either I- or Q-Channel input may be sampled by both ADCs
DES Sampling Clock Adjustment	The Clock Phase is adjusted automatically	Automatic Clock Phase control can be selected by setting bit 14 in the DES Enable register (Dh). The clock phase can also be adjusted manually through the Coarse & Fine registers (Eh and Fh)

The default state of the Extended Control Mode is set upon power-on reset (internally performed by the device) and is shown in Table 3.

Table 3. Extended Control Mode Operation (Pin 14 Floating)

Feature	Extended Control Mode Default State		
SDR or DDR Clocking	DDR Clocking		
DDR Clock Phase	Data changes with DCLK edge (0° phase)		
LVDS Output Amplitude	Normal amplitude (710 mV <sub>P-P</sub> )		
Calibration Delay	Short Delay		
Full-Scale Range	700 mV nominal for both channels		
Input Offset Adjust	No adjustment for either channel		
Dual Edge Sampling (DES)	Not enabled		

### THE SERIAL INTERFACE

The 3-pin serial interface is enabled only when the device is in the Extended Control mode. The pins of this interface are Serial Clock (SCLK), Serial Data (SDATA) and Serial Interface Chip Select (SCS) Eight write only registers are accessible through this serial interface.

**SCS**: This signal should be asserted low while accessing a register through the serial interface. Setup and hold times with respect to the SCLK must be observed.

**SCLK**: Serial data input is accepted with the rising edge of this signal.

**SDATA:** Each register access requires a specific 32-bit pattern at this input. This pattern consists of a header, register address and register value. The data is shifted in MSB first. Setup and hold times with respect to the SCLK must be observed. See the Timing Diagrams.

Each Register access consists of 32 bits, as shown in Figure 6 of the Timing Diagrams. The fixed header pattern is 0000 0000 0001 (eleven zeros followed by a 1). The loading sequence is such that a "0" is loaded first. These 12 bits form the header. The next 4 bits are the address of the register that is to be written to and the last 16 bits are the data written to the addressed register. The addresses of the various registers are indicated in Table 4.

Refer to the REGISTER DESCRIPTION for information on the data to be written to the registers.

Subsequent register accesses may be performed immediately, starting with the 33rd SCLK. This means that the SCS input does not have to be de-asserted and asserted again between register addresses. It is possible, although not recommended, to keep the SCS input permanently enabled (at a logic low) when using extended control.

**IMPORTANT NOTE:** The Serial Interface should not be used when calibrating the ADC. Doing so will impair the performance of the device until it is re-calibrated correctly. Programming the serial registers will also reduce dynamic performance of the ADC for the duration of the register access time. **Not recommended for use in Radiation Environments, See APPLICATIONS IN RADIATION ENVIRONMENTS.** 



### **Table 4. Register Addresses**

	4-Bit Address									
	Loading Sequence: A3 loaded after H0, A0 loaded last									
A3	A2	A1	A0	Hex	Register Addressed					
0	0	0	0	0h	Reserved					
0	0	0	1	1h	Configuration					
0	0	1	0	2h	"I" Ch Offset					
0	0	1	1	3h	"I" Ch Full-Scale Voltage Adjust					
0	1	0	0	4h	Reserved					
0	1	0	1	5h	Reserved					
0	1	1	0	6h	Reserved					
0	1	1	1	7h	Reserved					
1	0	0	0	8h	Reserved					
1	0	0	1	9h	Reserved					
1	0	1	0	Ah	"Q" Ch Offset					
1	0	1	1	Bh	"Q" Ch Full-Scale Voltage Adjust					
1	1	0	0	Ch	Reserved					
1	1	0	1	Dh	DES Enable					
1	1	1	0	Eh	DES Coarse Adjust					
1	1	1	1	Fh	DES Fine Adjust					

### **REGISTER DESCRIPTION**

Eight write-only registers provide several control and configuration options in the Extended Control Mode. These registers have no effect when the device is in the Normal Control Mode. Each register description below also shows the Power-On Reset (POR) state of each control bit.

**Table 5. Configuration Register** 

Addr: 1h (0001k	o)						W only (0xB2FF)
D15	D14	D13	D12	D11	D10	D9	D8
1	0	1	DCS	DCP	nDE	OV	OE
D7	D6	D5	D4	D3	D2	D1	D0
1	1	1	1	1	1	1	1

Bit 15	Must be set to 1b					
Bit 14	Must be set to 0b					
Bit 13	Must be set to 1b					
Bit 12	DCS:Duty Cycle Stabilizer. When this bit is set to 1b, a duty cycle stabilization circuit is applied to the clock input. When this bit is set to 0b the stabilization circuit is disabled.					
	POR State: 1b					
Bit 11	DCP: DDR Clock Phase. This bit only has an effect in the DDR mode. When this bit is set to 0b, the DCLK edges are time-aligned with the data bus edges ("0° Phase"). When this bit is set to 1b, the DCLK edges are placed in the middle of the data bit-cells ("90° Phase"), using the one-half speed DCLK shown in Figure 5 as the phase reference.					
	POR State: 0b					
Bit 10	nDE: DDR Enable. When this bit is set to 0b, data bus clocking follows the DDR (Dual Data Rate) mode whereby a data word is output with each rising and falling edge of DCLK. When this bit is set to a 1b, data bus clocking follows the SDR (single data rate) mode whereby each data word is output with either the rising or falling edge of DCLK, as determined by the OutEdge bit.					
	POR State: 0b					

SNAS352F - JANUARY 2007-REVISED NOVEMBER 2009



Bit 9	OV: Output Voltage. This bit determines the LVDS outputs' voltage amplitude and has the same function as the OutV pin that is used in the normal control mode. When this bit is set to 1b, the standard output amplitude of 710 mV <sub>P-P</sub> is used. When this bit is set to 0b, the reduced output amplitude of 510 mV <sub>P-P</sub> is used.
	POR State: 1b
Bit 8	OE: Output Edge. This bit selects the DCLK edge with which the data words transition in the SDR mode and has the same effect as the OutEdge pin in the normal control mode. When this bit is 1, the data outputs change with the rising edge of DCLK+. When this bit is 0, the data output change with the falling edge of DCLK+.
	POR State: 0b
Bits 7:0	Must be set to 1b.

# Table 6. I-Channel Offset

Addr: 2h (0010b)							W only (0x007F)	
D15	D14	D13	D12	D11	D10	D9	D8	
(MSB)			Offset	Value			(LSB)	
D7	D6	D5	D4	D3	D2	D1	D0	
Sign	1	1	1	1	1	1	1	
Bits 15:8	field. ( provid	Offset Value. The input offset of the I-Channel ADC is adjusted linearly and monotonically by the value in this field. 00h provides a nominal zero offset, while FFh provides a nominal 45 mV of offset. Thus, each code step provides 0.176 mV of offset.  POR State: 0000 0000 b						
Bit 7 Sign b		Sign bit. 0b gives positive offset, 1b gives negative offset.						
POR S		State: 0b						
Bit 6:0	Must I	oe set to 1b						

### Table 7. I-Channel Full-Scale Voltage Adjust

Addr: 3h (0011b)						'	W only (0x807F)
D15	D14	D13	D12	D11	D10	D9	D8
	D14	DIS	DIZ		DIO	Da	Do
(MSB)	Adjust Value						
D7	D6	D5	D4	D3	D2	D1	D0
(LSB)	1	1	1	1	1	1	1
							mvp.p dillerenda
	value.						mV <sub>P-P</sub> differential
	0000 00	00 0		560mV <sub>P-P</sub>			TIVP-P differentia
		00 0 00 0 Default Valu	ıe	560mV <sub>P-P</sub>			nvp.p umerenila
		00 0 Default Valu	le				nvp.p dinerentia
	1000 00 1111 11 For best 1110 00	00 0 Default Value 11 1 control of the control of t	is recommended	700mV <sub>P-P</sub>	The remaining ±5°	% headroom allov	00100 000 0b to
	1000 00 1111 11 For best 1110 00 own full	00 0 Default Value 11 1 control of the control of t	is recommended ne amount of ad gain adjustmer	700mV <sub>P-P</sub> 840mV <sub>P-P</sub> I that the value in t ustment to ±15%. T	The remaining ±5°	% headroom allov	00100 000 0b to

# Table 8. Q-Channel Offset

Addr: Ah (1010b)	W only (0x007F)
------------------	-----------------



### www.ti.com

SNAS352F - JANUARY 2007 - REVISED NOVEMBER 2009

D15	D14	D13	D12	D11	D10	D9	D8
(MSB)			Offset	Value	•		(LSB)
D7	D6	D5	D4	D3	D2	D1	D0
Sign	1	1	1	1	1	1	1

Bit 15:8	Offset Value. The input offset of the Q-Channel ADC is adjusted linearly and monotonically by the value in this field. 00h provides a nominal zero offset, while FFh provides a nominal 45 mV of offset. Thus, each code step provides about 0.176 mV of offset.
	POR State: 0000 0000 b
Bit 7	Sign bit. 0b gives positive offset, 1b gives negative offset.
	POR State: 0b
Bit 6:0	Must be set to 1b

# Table 9. Q-Channel Full-Scale Voltage Adjust

Addr: Bh (1011b)							W only (0x807F)
D15	D14	D13	D12	D11	D10	D9	D8
(MSB)		Adjust Value					
D7	D6	D5	D4	D3	D2	D1	D0
(LSB)	1	1	1	1	1	1	1

Bit 15:7	Full Scale Voltage Adjust Value. The input full-scale voltage or gain of the I-Channel ADC is adjusted linearly and monotonically with a 9 bit data value. The adjustment range is ±20% of the nominal 700 mV <sub>P-P</sub> differential value.					
	0000 0000 0	560mV <sub>P-P</sub>				
	1000 0000 0	700mV <sub>P-P</sub>				
	1111 1111 1 840mV <sub>P-P</sub>					
	For best performance, it is recommended that the value in this field be limited to the range of 00100 000 0b to 1110 0000 0b. i.e., limit the amount of adjustment to ±15%. The remaining ±5% headroom allows for the ADC's own full scale variation. A gain adjustment does not require ADC re-calibration.					
	POR State: 1000 0000 0b (no adjustment)					
Bits 6:0	Must be set to 1b					



#### Table 10. DES Enable

Addr: Dh (1101	b)					1	W only (0x3FFF)
D15	D14	D13	D12	D11	D10	D9	D8
DEN	ACP	1	1	1	1	1	1
D7	D6	D5	D4	D3	D2	D1	D0
1	1	1	1	1	1	1	1

Bit 15	DES Enable. Setting this bit to 1b enables the Dual Edge Sampling mode. In this mode the ADCs in this device are used to sample and convert the same analog input in a time-interleaved manner, accomplishing a sampling rate of twice the input clock rate. When this bit is set to 0b, the device operates in the normal dual channel mode.
	POR State: 0b
Bit 14	Automatic Clock Phase Control. (ACP) Setting this bit to 1b enables the Automatic Clock Phase Control. In this mode the DES Coarse and Fine manual controls are disabled. A phase detection circuit continually adjusts the I and Q sampling edges to be 180 degrees out of phase. When this bit is set to 0b, the sample (input) clock delay between the I and Q channels is set manually using the DES Coarse and Fine Adjust registers. (See THE CLOCK INPUTS for important application information) Using the ACP Control option is recommended over the manual DES settings.
	POR State: 0b
Bits 13:0	Must be set to 1b

# **Note Regarding Extended Mode Offset Correction**

When using the I or Q channel Offset Adjust registers, the following information should be noted.

For offset values of +0000 0000 and -0000 0000, the actual offset is not the same. By changing only the sign bit in this case, an offset step in the digital output code of about 1/10th of an LSB is experienced. This is shown more clearly in the Figure below.




Figure 40. Extended Mode Offset Behaviour



#### MULTIPLE ADC SYNCHRONIZATION

The ADC08D1000QML has the capability to precisely reset its sampling clock input to DCLK output relationship as determined by the user-supplied DCLK\_RST pulse. This allows multiple ADCs in a system to have their DCLK (and data) outputs transition at the same time with respect to the shared CLK input that they all use for sampling.

The DCLK\_RST signal must observe some timing requirements that are shown in Figure 7, Figure 8 and Figure 9 of the Timing Diagrams. The DCLK\_RST pulse must be of a minimum width and its deassertion edge must observe setup and hold times with respect to the CLK input rising edge. These times are specified in the AC Electrical Characteristics Table.

The DCLK\_RST signal can be asserted asynchronous to the input clock. If DCLK\_RST is asserted, the DCLK output is held in a designated state. The state in which DCLK is held during the reset period is determined by the mode of operation (SDR/DDR) and the setting of the Output Edge configuration pin or bit. (Refer to Figure 7, Figure 8 and Figure 9 for the DCLK reset state conditions). Therefore, depending upon when the DCLK\_RST signal is asserted, there may be a narrow pulse on the DCLK line during this reset event. When the DCLK\_RST signal is de-asserted in synchronization with the CLK rising edge, the next CLK falling edge synchronizes the DCLK output with those of other ADC08D1000QMLs in the system. The DCLK output is enabled again after a constant delay (relative to the input clock frequency) which is equal to the CLK input to DCLK output delay (t<sub>SD</sub>). The device always exhibits this delay characteristic in normal operation.

The DCLK-RST pin should NOT be brought high while the calibration process is running (while CalRun is high). Doing so could cause a digital glitch in the digital circuitry, resulting in corruption and invalidation of the calibration.

# **Applications Information**

### **APPLICATIONS IN RADIATION ENVIRONMENTS**

Applying the ADC08D1000 in a radiation environment should be done with careful consideration to that environment. The QMLV version of this part has been rated to tolerate a high total dose of ionizing radiation by test method 1019 of MIL-STD-883, it is also designed to withstand SEE (Single Event Effects) and greatly mitigate these effects, however, there are still some recommendations and cautions.

**Extended Control mode**, using the serial interface feature, should not be used in radiation environments. This is because the D Flip Flops used in the serial interface registers are not SET/SEU immune. Also, the serial interface is a write-only interface, and a register that has changed states cannot be read back and, therefore, is undetectable.

**Dual-Edge Sampling Mode,** DES Mode should not be used in radiation environments. This is because the cal circuitry when in DES Mode is not SET/SEU (Single Event Transient and Single Event Upset, both are types of SEE effects) immune.

**Floating pins.** There are three tri-level pins which activate the following modes when left floating: FSR/ECE, OutEdge/DDR/SDATA, and CalDly/DES/SCS. As pointed out in the last paragraph, Extended Control mode should not be used in radiation environments, thus, the FSR/ECE mode should not be left floating or connected to Va/2, either a logic high or logic low should be applied to this pin. If DDR or DES modes need to be used, then it is strongly recommended that the floating method of establishing Va/2 on these pins not be employed. Due to the potential of increased leakage of the input protection diodes after large ionizing doses, the midpoint voltage (Va/2 or 0.95V) should be voltage forced or formed with a resistor divider from the analog supply to ground with two 2K ohm resistors. The internal voltage divider resistors provide too little current to set the midpoint voltage reliably in radiation environments.

The CAL pin should be kept at a logic high at all times during normal operation in radiation environments and calibration should be manually initiated by bringing the CAL pin low and then back high again. This will prevent POR initiated calibrations. The POR circuit is susceptible to SET. A POR during normal operation would not be acceptable if it erased register settings or initiated a calibration cycle (during the calibration cycle the ADC cannot be used). In the QML version of the ADC08D1000, all internal registers resets will be connected to the calibration reset, not POR. Therefore, a POR during normal operations will not cause registers to be erased and, if the CAL pin is kept at a logic high, POR initiated calibration will not occur. In the QML version of the ADC08D1000, the



POR will only be used to reset the self-timer for AUTO-CAL, whose functionality is maintained for backwards compatibility only. Also, when using the QML version of the ADC08D1000 as described in this paragraph, the calibration registers will initiate randomly and remain so until a calibration cycle has been initiated. In the QML version of the ADC08D1000, with the CAL pin kept at a logic high, a POR event essentially does "nothing" except reset the AUTO-CAL self-timer.

#### THE REFERENCE VOLTAGE

The voltage reference for the ADC08D1000 is derived from a 1.254V bandgap reference, a buffered version of which is made available at pin 31,  $V_{BG}$  for user convenience and has an output current capability of  $\pm 100~\mu A$ . This reference voltage should be buffered if more current is required.

The internal bandgap-derived reference voltage has a nominal value of 650 mV or 870 mV, as determined by the FSR pin and described in The Analog Inputs.

There is no provision for the use of an external reference voltage, but the full-scale input voltage can be adjusted through a Configuration Register in the Extended Control mode, as explained in NORMAL/EXTENDED CONTROL.

Differential input signals up to the chosen full-scale level will be digitized to 8 bits. Signal excursions beyond the full-scale range will be clipped at the output. These large signal excursions will also activate the OR output for the time that the signal is out of range. See Out Of Range (OR) Indication.

One extra feature of the  $V_{BG}$  pin is that it can be used to raise the common mode voltage level of the LVDS outputs. The output offset voltage ( $V_{OS}$ ) is typically 800mV when the  $V_{BG}$  pin is used as an output or left unconnected. To raise the LVDS offset voltage to a typical value of 1200mV the  $V_{BG}$  pin can be connected directly to the supply rails.

### THE ANALOG INPUT

The analog input is a differential one to which the signal source may be a.c. coupled or d.c. coupled. The full-scale input range is selected with the FSR pin to be 650 mV<sub>P-P</sub> or 870 mV<sub>P-P</sub>, or can be adjusted to values between 560 mV<sub>P-P</sub> and 840 mV<sub>P-P</sub> in the Extended Control mode through the Serial Interface. For best performance, it is recommended that the full-scale range be kept between 595 mV<sub>P-P</sub> and 805 mV<sub>P-P</sub> in the Extended Control mode.

Table 11 gives the input to output relationship with the FSR pin high and the normal (non-extended) mode is used. With the FSR pin grounded, the millivolt values in Table 11 are reduced to 75% of the values indicated. In the Enhanced Control Mode, these values will be determined by the full scale range and offset settings in the Control Registers.

Table 11. DIFFERENTIAL INPUT TO OUTPUT RELATIONSHIP (Non-Extended Control Mode, FSR High)

V <sub>IN</sub> +	V <sub>IN</sub> -	Output Code
V <sub>CM</sub> - 217.5mV	V <sub>CM</sub> + 217.5mV	0000 0000
V <sub>CM</sub> - 109 mV	V <sub>CM</sub> + 109 mV	0100 0000
V <sub>CM</sub>	V <sub>CM</sub>	0111 1111 / 1000 0000
V <sub>CM</sub> + 109 mV	V <sub>CM</sub> -109 mV	1100 0000
V <sub>CM</sub> + 217.5mV	V <sub>CM</sub> - 217.5mV	1111 1111

The buffered analog inputs simplify the task of driving these inputs and the RC pole that is generally used at sampling ADC inputs is not required. If it is desired to use an amplifier circuit before the ADC, use care in choosing an amplifier with adequate noise and distortion performance and adequate gain at the frequencies used for the application.

Note that a precise d.c. common mode voltage must be present at the ADC inputs. This common mode voltage,  $V_{CMO}$ , is provided on-chip when a.c. input coupling is used and the input signal is a.c. coupled to the ADC.

When the inputs are a.c. coupled, the  $V_{CMO}$  output *must* be grounded, as shown in Figure 41. This causes the on-chip  $V_{CMO}$  voltage to be connected to the inputs through on-chip 50k-Ohm resistors.

**IMPORTANT NOTE**: An Analog input channel that is not used (e.g. in DES Mode) should be left floating when the inputs are a.c. coupled. Do not connect an unused analog input to ground.






Figure 41. Differential Input Drive

When the d.c. coupled mode is used, a common mode voltage must be provided at the differential inputs. This common mode voltage should track the  $V_{CMO}$  output pin. Note that the  $V_{CMO}$  output potential will change with temperature. The common mode output of the driving device should track this change.

**IMPORTANT NOTE:** An analog input channel that is not used (e.g. in DES Mode) should be tied to the  $V_{CMO}$  voltage when the inputs are d.c coupled. Do not connect unused analog inputs to ground.

Full-scale distortion performance falls off rapidly as the input common mode voltage deviates from  $V_{CMO}$ . This is a direct result of using a very low supply voltage to minimize power. Keep the input common voltage within 50 mV of  $V_{CMO}$ .

Performance is as good in the d.c. coupled mode as it is in the a.c. coupled mode, provided the input common mode voltage at both analog inputs remain within 50 mV of  $V_{CMO}$ .

If d.c. coupling is used, it is best to servo the input common mode voltage, using the  $V_{CMO}$  pin, to maintain optimum performance. An example of this type of circuit is shown in Figure 42.




Figure 42. Example of Servoing the Analog Input with V<sub>CMO</sub>

One such circuit should be used in front of the  $V_{IN}+$  input and another in front of the  $V_{IN}-$  input. In that figure,  $R_{D1}$ ,  $R_{D2}$  and  $R_{D3}$  are used to divide the  $V_{CMO}$  potential so that, after being gained up by the amplifier, the input common mode voltage is equal to  $V_{CMO}$  from the ADC.  $R_{D1}$  and  $R_{D2}$  are split to allow the bypass capacitor to isolate the input signal from  $V_{CMO}$ .  $R_{IN}$ ,  $R_{D2}$  and  $R_{D3}$  will divide the input signal, if necessary. Capacitor "C" in Figure 42 should be chosen to keep any component of the input signal from affecting  $V_{CMO}$ .

Be sure that the current drawn from the  $V_{CMO}$  output does not exceed 100  $\mu$ A.

The Input impedance in the d.c. coupled mode ( $V_{CMO}$  pin not grounded) consists of a precision  $100\Omega$  resistor between  $V_{IN}$ + and  $V_{IN}$ - and a capacitance from each of these inputs to ground. In the a.c. coupled mode the input appears the same except there is also a resistor of 50K between each analog input pin and the  $V_{CMO}$  potential.

Driving the inputs beyond full scale will result in a saturation or clipping of the reconstructed output.

# Handling Single-Ended Input Signals

There is no provision for the ADC08D1000 to adequately process single-ended input signals. The best way to handle single-ended signals is to convert them to differential signals before presenting them to the ADC. The easiest way to accomplish single-ended to differential signal conversion is with an appropriate balun-connected transformer, as shown in Figure 43.

Copyright © 2007–2009, Texas Instruments Incorporated

Submit Documentation Feedback






Figure 43. Single-Ended To Differential Signal Conversion With A Balun-Connected Transformer

The 100 Ohm external resistor placed accross the output terminals of the balun in parallel with the ADC08D1000's on-chip 100 Ohm resistor makes a 50 Ohms differential impedance at the balun output. Or, 25 Ohms to virtual ground at each of the balun output terminals.

Looking into the balun, the source sees the impedance of the first coil in series with the impedance at the output of that coil. Since the transformer has a 1:1 turns ratio, the impedance across the first coil is exactly the same as that at the output of the second coil, namely 25 Ohms to virtual ground. So, the 25 Ohms across the first coil in series with the 25 Ohms at its output gives 50 Ohms total impedance to match the source.

# Out Of Range (OR) Indication

When the conversion result is clipped the Out of Range output is activated such that OR+ goes high and OR-goes low. This output is active as long as accurate data on either or both of the buses would be outside the range of 00h to FFh.

### Full-Scale Input Range

As with all A/D Converters, the input range is determined by the value of the ADC's reference voltage. The reference voltage of the ADC08D1000 is derived from an internal band-gap reference. The FSR pin controls the effective reference voltage of the ADC08D1000 such that the differential full-scale input range at the analog inputs is 870 mV<sub>P-P</sub> with the FSR pin high, or is 650 mV<sub>P-P</sub> with FSR pin low. Best SNR is obtained with FSR high, but better distortion and SFDR are obtained with the FSR pin low.

#### THE CLOCK INPUTS

The ADC08D1000 has differential LVDS clock inputs, CLK+ and CLK-, which must be driven with an a.c. coupled, differential clock signal. Although the ADC08D1000 is tested and its performance is guaranteed with a differential 1.0 GHz clock, it typically will function well with input clock frequencies indicated in the Electrical Characteristics Table. The clock inputs are internally terminated and biased. The input clock signal must be capacitively coupled to the clock pins as indicated in Figure 44.

Operation up to the sample rates indicated in the Electrical Characteristics Table is typically possible if the maximum ambient temperatures indicated are not exceeded. Operating at higher sample rates than indicated for the given ambient temperature may result in reduced device reliability and product lifetime. This is because of the higher power consumption and die temperatures at high sample rates. Important also for reliability is proper thermal management . See Thermal Management.




Figure 44. Differential (LVDS) Input Clock Connection

The differential input clock line pair should have a characteristic impedance of  $100\Omega$  and (when using a balun), be terminated at the clock source in that  $(100\Omega)$  characteristic impedance. The input clock line should be as short and as direct as possible. The ADC08D1000 clock input is internally terminated with an untrimmed  $100\Omega$  resistor.



Insufficient input clock levels will result in poor dynamic performance. Excessively high input clock levels could cause a change in the analog input offset voltage. To avoid these problems, keep the input clock level within the range specified in the Electrical Characteristics Table.

The low and high times of the input clock signal can affect the performance of any A/D Converter. The ADC08D1000 features a duty cycle clock correction circuit which can maintain performance over temperature even in DES mode. The ADC will meet its performance specification if the input clock high and low times are maintained within the range (30/70% ratio).

High speed, high performance ADCs such as the ADC08D1000 require a very stable input clock signal with minimum phase noise or jitter. ADC jitter requirements are defined by the ADC resolution (number of bits), maximum ADC input frequency and the input signal amplitude relative to the ADC input full scale range. The maximum jitter (the sum of the jitter from all sources) allowed to prevent a jitter-induced reduction in SNR is found to be

$$t_{J(MAX)} = (V_{IN(P-P)}/V_{INFSR}) \times (1/(2^{(N+1)} \times \pi \times f_{IN}))$$
(3)

where  $t_{J(MAX)}$  is the rms total of all jitter sources in seconds,  $V_{IN(P-P)}$  is the peak-to-peak analog input signal,  $V_{INFSR}$  is the full-scale range of the ADC, "N" is the ADC resolution in bits and  $f_{IN}$  is the maximum input frequency, in Hertz, to the ADC analog input.

Note that the maximum jitter described above is the arithmetic sum of the jitter from all sources, including that in the ADC input clock, that added by the system to the ADC input clock and input signals and that added by the ADC itself. Since the effective jitter added by the ADC is beyond user control, the best the user can do is to keep the sum of the externally added input clock jitter and the jitter added by the analog circuitry to the analog signal to a minimum.

Input clock amplitudes above those specified in the Electrical Characteristics Table may result in increased input offset voltage. This would cause the converter to produce an output code other than the expected 127/128 when both input pins are at the same potential.

#### **CONTROL PINS**

Six control pins (without the use of the serial interface) provide a wide range of possibilities in the operation of the ADC08D1000 and facilitate its use. These control pins provide Full-Scale Input Range setting, Self Calibration, Calibration Delay, Output Edge Synchronization choice, LVDS Output Level choice and a Power Down feature.

#### Full-Scale Input Range Setting

The input full-scale range can be selected to be either 650 mV<sub>P-P</sub> or 870 mV<sub>P-P</sub>, as selected with the FSR control input (pin 14) in the Normal Mode of operation. In the Extended Control Mode, the input full-scale range may be set to be anywhere from 560 mV<sub>P-P</sub> to 840 mV<sub>P-P</sub>. See THE REFERENCE VOLTAGE for more information.

#### Self Calibration

The ADC08D1000 self-calibration must be run to achieve specified performance. The calibration procedure is run upon power-up and can be run any time on command. The calibration procedure is exactly the same whether there is an input clock present upon power up or if the clock begins some time after application of power. The CalRun output indicator is high while a calibration is in progress. Note that DCLK outputs are not active during a calibration cycle.

### **Power-On Calibration**

Power-on calibration begins after a time delay following the application of power. This time delay is determined by the setting of CalDly, as described in Calibration Delay below.

The calibration process will not be performed if the CAL pin is high at power up. In this case, the calibration cycle will not begin until the on-command calibration conditions are met. The ADC08D1000 will function with the CAL pin held high at power up, but no calibration will be done and performance will be impaired. A manual calibration, however, may be performed after powering up with the CAL pin high. See On-Command Calibration.



The internal power-on calibration circuitry comes up in an unknown logic state. If the input clock is not running at power up and the power on calibration circuitry is active, it will hold the analog circuitry in power down and the power consumption will typically be less than 200 mW. The power consumption will be normal after the clock starts.

#### **On-Command Calibration**

On-command calibration may be run at any time in NORMAL (non-DES) mode only. Do not run a calibration while operating the ADC in Auto DES Mode.

If the ADC is operating in Auto DES mode and a calibration cycle is required then the controlling application should bring the ADC into normal (non DES) mode before an On Command calibration is initiated. Once calibration has completed, the ADC can be put back into Auto DES mode.

To initiate an on-command calibration, bring the CAL pin high for a minimum of 640 input clock cycles after it has been low for a minimum of 640 input clock cycles. Holding the CAL pin high upon power up will prevent execution of power-on calibration until the CAL pin is low for a minimum of 640 input clock cycles, then brought high for a minimum of another 640 input clock cycles. The calibration cycle will begin 640 input clock cycles after the CAL pin is thus brought high. The CalRun signal should be monitored to determine when the calibration cycle has completed.

The minimum 640 input clock cycle sequences are required to ensure that random noise does not cause a calibration to begin when it is not desired. As mentioned in Self-Calibration for best performance, a self calibration should be performed 20 seconds or more after power up and repeated when the operating temperature changes significantly, according to the particular system performance requirements. As can be seen in the following figures ENOB drops slightly with increasing junction temperature, and a self calibration eliminates the change. In the first example (see Figure 45), a sample clock of 1GSPS is used to capture a full-scale 749MHz signal at the I-channel input as the junction temperature (T<sub>J</sub>) is increased from 65°C to 125°C with no intermediate calibration cycles. The vertical line at 125°C is the result of an on-command calibration cycle that essentially eliminates the drop in ENOB. Of course, calibration cycles can be run more often, at smaller intervals of temperature change, if system design specifications require it. In the second example (see Figure 46), the test method is the same and the I-channel input signal is 249MHz. The variation in ENOB vs. T<sub>J</sub> has a smaller range then the previous example, and is again removed by an on-command calibration cycle at the maximum test temperature.




Figure 45. ENOB vs. Junction Temperature, 749MHz input






Figure 46. ENOB vs. Junction Temperature, 249MHz input

### **Calibration Delay**

The CalDly input (pin 127) is used to select one of two delay times after the application of power to the start of calibration, as described in Self-Calibration. The calibration delay values allow the power supply to come up and stabilize before calibration takes place. With no delay or insufficient delay, calibration would begin before the power supply is stabilized at its operating value and result in non-optimal calibration coefficients. If the PD pin is high upon power-up, the calibration delay counter will be disabled until the PD pin is brought low. Therefore, holding the PD pin high during power up will further delay the start of the power-up calibration cycle. The best setting of the CalDly pin depends upon the power-on settling time of the power supply.

Note that the calibration delay selection is not possible in the Extended Control mode and the short delay time is used.

### **Output Edge Synchronization**

DCLK signals are available to help latch the converter output data into external circuitry. The output data can be synchronized with either edge of these DCLK signals. That is, the output data transition can be set to occur with either the rising edge or the falling edge of the DCLK signal, so that either edge of that DCLK signal can be used to latch the output data into the receiving circuit.

When OutEdge (pin 4) is high, the output data is synchronized with (changes with) the rising edge of the DCLK+ (pin 82). When OutEdge is low, the output data is synchronized with the falling edge of DCLK+.

At the very high speeds of which the ADC08D1000 is capable, slight differences in the lengths of the DCLK and data lines can mean the difference between successful and erroneous data capture. The OutEdge pin is used to capture data on the DCLK edge that best suits the application circuit and layout.

#### LVDS Output Level Control

The output level can be set to one of two levels with OutV (pin3). The strength of the output drivers is greater with OutV high. With OutV low there is less power consumption in the output drivers, but the lower output level means decreased noise immunity.

For short LVDS lines and low noise systems, satisfactory performance may be realized with the OutV input low. If the LVDS lines are long and/or the system in which the ADC08D1000QML is used is noisy, it may be necessary to tie the OutV pin high.

### Dual Edge Sampling

### The Dual Edge Sampling mode should not be used in radiation environments.

The Dual Edge Sampling (DES) feature causes one of the two input pairs to be routed to both ADCs. The other input pair is deactivated. One of the ADCs samples the input signal on one input clock edge (duty cycle corrected), the other samples the input signal on the other input clock edge (duty cycle corrected). The result is a 1:4 demultiplexed output with a sample rate that is twice the input clock frequency.



To use this feature in the non-enhanced control mode, allow pin 127 to float and the signal at the "I" channel input will be sampled by both converters. The Calibration Delay will then only be a short delay.

In the enhanced control mode, either input may be used for dual edge sampling. See Dual-Edge Sampling.

#### **IMPORTANT NOTES:**

- 1) For the Extended Control Mode When using the Automatic Clock Phase Control feature in dual edge sampling mode, it is important that the automatic phase control is disabled (set bit 14 of DES Enable register Dh to 0) before the ADC is powered up. Not doing so may cause the device not to wakeup from the powerdown state.
- 2) For the Non-Extended Control Mode When the ADC08D1000 is powered up and DES mode is required, ensure that pin 127 (CalDly/DES/SCS) is initially pulled low during or after the power up sequence. The pin can then be allowed to float or be tied to  $V_A$  / 2 to enter the DES mode. This will ensure that the part enters the DES mode correctly.
- 3) The automatic phase control should also be disabled if the input clock is interrupted or stopped for any reason. This is also the case if a large abrupt change in the clock frequency occurs.
- 4) If a calibration of the ADC is required in Auto DES mode, the device must be returned to the Normal Mode of operation before performing a calibration cycle. Once the Calibration has been completed, the device can be returned to the Auto DES mode and operation can resume.

### Power Down Feature

The Power Down pins (PD and PDQ) allow the ADC08D1000 to be entirely powered down (PD) or the "Q" channel to be powered down and the "I" channel to remain active. See Power Down for details on the power down feature.

The digital data (+/-) output pins are put into a high impedance state when the PD pin for the respective channel is high. Upon return to normal operation, the pipeline will contain meaningless information and must be flushed.

If the PD input is brought high while a calibration is running, the device will not go into power down until the calibration sequence is complete. However, if power is applied and PD is already high, the device will not begin the calibration sequence until the PD input goes low. If a manual calibration is requested while the device is powered down, the calibration will not begin at all. That is, the manual calibration input is completely ignored in the power down state.

### THE DIGITAL OUTPUTS

The ADC08D1000 demultiplexes the output data of each of the two ADCs on the die onto two LVDS output buses (total of four buses, two for each ADC). For each of the two converters, the results of successive conversions started on the odd falling edges of the CLK+ pin are available on one of the two LVDS buses, while the results of conversions started on the even falling edges of the CLK+ pin are available on the other LVDS bus. This means that, the word rate at each LVDS bus is 1/2 the ADC08D1000 input clock rate and the two buses must be multiplexed to obtain the entire 1 GSPS conversion result.

Since the minimum recommended input clock rate for this device is 200 MSPS (normal non DES mode), the effective rate can be reduced to as low as 100 MSPS by using the results available on just one of the two LVDS buses and a 200 MHz input clock, decimating the 200 MSPS data by two.

There is one LVDS output clock pair (DCLK+/-) available for use to latch the LVDS outputs on all buses. Whether the data is sent at the rising or falling edge of DCLK is determined by the sense of the OutEdge pin, as described in Output Edge Synchronization.

DDR (Double Data Rate) clocking can also be used. In this mode a word of data is presented with each edge of DCLK, reducing the DCLK frequency to 1/4 the input clock frequency. See the Timing Diagrams section for details.

The OutV pin is used to set the LVDS differential output levels. See LVDS Output Level Control.

The output format is Offset Binary. Accordingly, a full-scale input level with  $V_{IN}$ + positive with respect to  $V_{IN}$ - will produce an output code of all ones, a full-scale input level with  $V_{IN}$ - positive with respect to  $V_{IN}$ + will produce an output code of all zeros and when  $V_{IN}$ + and  $V_{IN}$ - are equal, the output code will vary between codes 127 and 128.

www.ti.com

#### **POWER CONSIDERATIONS**

A/D converters draw sufficient transient current to corrupt their own power supplies if not adequately bypassed. A 33  $\mu$ F capacitor should be placed within an inch (2.5 cm) of the A/D converter power pins. A 0.1  $\mu$ F capacitor should be placed as close as possible to each  $V_A$  pin, preferably within one-half centimeter. Leadless chip capacitors are preferred because they have low lead inductance.

The  $V_A$  and  $V_{DR}$  supply pins should be isolated from each other to prevent any digital noise from being coupled into the analog portions of the ADC. A ferrite choke, such as the JW Miller FB20009-3B, is recommended between these supply lines when a common source is used for them.

As is the case with all high speed converters, the ADC08D1000 should be assumed to have little power supply noise rejection. Any power supply used for digital circuitry in a system where a lot of digital power is being consumed should not be used to supply power to the ADC08D1000. The ADC supplies should be the same supply used for other analog circuitry, if not a dedicated supply.

### Supply Voltage

The ADC08D1000 is specified to operate with a supply voltage of 1.9V ±0.1V. It is very important to note that, while this device will function with slightly higher supply voltages, these higher supply voltages may reduce product lifetime.

No pin should ever have a voltage on it that is in excess of the supply voltage or below ground by more than 150 mV, not even on a transient basis. This can be a problem upon application of power and power shut-down. Be sure that the supplies to circuits driving any of the input pins, analog or digital, do not come up any faster than does the voltage at the ADC08D1000QML power pins.

The Absolute Maximum Ratings should be strictly observed, even during power up and power down. A power supply that produces a voltage spike at turn-on and/or turn-off of power can destroy the ADC08D1000. The circuit of Figure 47 will provide supply overshoot protection.

Many linear regulators will produce output spiking at power-on unless there is a minimum load provided. Active devices draw very little current until their supply voltages reach a few hundred millivolts. The result can be a turn-on spike that can destroy the ADC08D1000, unless a minimum load is provided for the supply. The  $100\Omega$  resistor at the regulator output provides a minimum output current during power-up to ensure there is no turn-on spiking.

In the circuit of Figure 47, an LM317 linear regulator is satisfactory if its input supply voltage is 4V to 5V. If a 3.3V supply is used, an LM1086 linear regulator is recommended.




Figure 47. Non-Spiking Power Supply

The output drivers should have a supply voltage,  $V_{DR}$ , that is within the range specified in the Operating Ratings table. This voltage should not exceed the  $V_A$  supply voltage.

If the power is applied to the device without an input clock signal present, the current drawn by the device might be below 200 mA. This is because the ADC08D1000 gets reset through clocked logic and its initial state is unknown. If the reset logic comes up in the "on" state, it will cause most of the analog circuitry to be powered down, resulting in less than 100 mA of current draw. This current is greater than the power down current because not all of the ADC is powered down. The device current will be normal after the input clock is established.



### Thermal Management

The ADC08D1000 is capable of impressive speeds and performance at very low power levels for its speed. However, the power consumption is still high enough to require attention to thermal management. For reliability reasons, the die temperature should be kept to a maximum of 150°C. That is,  $T_A$  (ambient temperature) plus ADC power consumption times  $\theta_{IA}$  (junction to ambient thermal resistance) should not exceed 150°C.

Please note the following recommendations for mounting this device onto a PCB. This should be considered the starting point in PCB and assembly process development. It is recommended that the process be developed based upon past experience in package mounting.

The bottom of the package of the ADC08D1000 provides the primary heat removal path as well as excellent electrical grounding to the printed circuit board. The land pattern design for lead attachment to the PCB should be the same as for a conventional LQFP, but the bottom of the package must be attached to the board to remove the maximum amount of heat from the package, as well as to ensure best product parametric performance.

To maximize the removal of heat from the package, a thermal land pattern must be incorporated on the PC board within the footprint of the package. The bottom of the device must be soldered down to ensure adequate heat conduction out of the package. The land pattern for this exposed pad should be as large as the 600 x 600 mil bottom of the package and be located such that the bottom of the device is entirely over that thermal land pattern. This thermal land pattern should be electrically connected to ground.




Figure 48. Recommended Package Land Pattern

Since a large aperture opening may result in poor release, the aperture opening should be subdivided into an array of smaller openings, similar to the land pattern of Figure 48.

To minimize junction temperature, it is recommended that a simple heat sink be built into the PCB. This is done by including a copper area of about 2.25 square inches (14.52 square cm) on the opposite side of the PCB. This copper area may be plated or solder coated to prevent corrosion, but should not have a conformal coating, which could provide some thermal insulation. Thermal vias should be used to connect these top and bottom copper areas. These thermal vias act as "heat pipes" to carry the thermal energy from the device side of the board to the opposite side of the board where it can be more effectively dissipated. The use of approximately 100 thermal vias is recommended. Use of a higher weight if copper on the internal ground plane is recommended, (i.e.  $2_{OZ}$  instead of  $1_{OZ}$ , for thermal considerations only.

The thermal vias should be placed on a 61 mil grid spacing and have a diameter of 15 mil typically. These vias should be barrel plated to avoid solder wicking into the vias during the soldering process as this wicking could cause voids in the solder between the package exposed pad and the thermal land on the PCB. Such voids could increase the thermal resistance between the device and the thermal land on the board, which would cause the device to run hotter.

If it is desired to monitor die temperature, a temperature sensor may be mounted on the heat sink area of the board near the thermal vias. .Allow for a thermal gradient between the temperature sensor and the ADC08D1000 die of  $\theta_{J-PAD}$  times typical power consumption.

# LAYOUT AND GROUNDING

Proper grounding and proper routing of all signals are essential to ensure accurate conversion. A single ground plane should be used, instead of splitting the ground plane into analog and digital areas.



Since digital switching transients are composed largely of high frequency components, the skin effect tells us that total ground plane copper weight will have little effect upon the logic-generated noise. Total surface area is more important than is total ground plane volume. Coupling between the typically noisy digital circuitry and the sensitive analog circuitry can lead to poor performance that may seem impossible to isolate and remedy. The solution is to keep the analog circuitry well separated from the digital circuitry.

High power digital components should not be located on or near any linear component or power supply trace or plane that services analog or mixed signal components as the resulting common return current path could cause fluctuation in the analog input "ground" return of the ADC, causing excessive noise in the conversion result.

Generally, we assume that analog and digital lines should cross each other at 90° to avoid getting digital noise into the analog path. In high frequency systems, however, avoid crossing analog and digital lines altogether. The input clock lines should be isolated from ALL other lines, analog AND digital. The generally accepted 90° crossing should be avoided as even a little coupling can cause problems at high frequencies. Best performance at high frequencies is obtained with a straight signal path.

The analog input should be isolated from noisy signal traces to avoid coupling of spurious signals into the input. This is especially important with the low level drive required of the ADC08D1000. Any external component (e.g., a filter capacitor) connected between the converter's input and ground should be connected to a very clean point in the analog ground plane. All analog circuitry (input amplifiers, filters, etc.) should be separated from any digital components.

#### DYNAMIC PERFORMANCE

The ADC08D1000 is a.c. tested and its dynamic performance is guaranteed. To meet the published specifications and avoid jitter-induced noise, the clock source driving the CLK input must exhibit low rms jitter. The allowable jitter is a function of the input frequency and the input signal level, as described in THE CLOCK INPUTS.

It is good practice to keep the ADC input clock line as short as possible, to keep it well away from any other signals and to treat it as a transmission line. Other signals can introduce jitter into the input clock signal. The clock signal can also introduce noise into the analog path if not isolated from that path.

Best dynamic performance is obtained when the exposed pad at the back of the package has a good connection to ground. This is because this path from the die to ground is a lower impedance than offered by the package pins.

### **USING THE SERIAL INTERFACE**

The ADC08D1000 may be operated in the non-extended control (non-Serial Interface) mode or in the extended control mode. Table 12 and Table 13 describe the functions of pins 3, 4, 14 and 127 in the non-extended control mode and the extended control mode, respectively.

### Non-Extended Control Mode Operation

Non-extended control mode operation means that the Serial Interface is not active and all controllable functions are controlled with various pin settings. That is, the full-scale range and input coupling (a.c. or d.c.) are controlled with pin settings. The non-extended control mode is used by setting pin 14 high or low, as opposed to letting it float. Table 12 indicates the pin functions of the ADC08D1000 in the non-extended control mode.

Table 12. Non-Extended Control Mode Operation (Pin 14 High or Low)

Pin	Low	High	Floating
3	0.50 V <sub>P-P</sub> Output	0.70 V <sub>P-P</sub> Output	n/a
4	OutEdge = Neg	OutEdge = Pos	DDR
127	CalDly Low	CalDly High	DES
14	650 mV <sub>P-P</sub> input range	870 mV <sub>P-P</sub> input range	Extended Control Mode

Submit Documentation Feedback



Pin 3 can be either high or low in the non-extended control mode. Pin 14 must not be left floating to select this mode. See NORMAL/EXTENDED CONTROL for more information.

Pin 4 can be high or low or can be left floating in the non-extended control mode. In the non-extended control mode, pin 4 high or low defines the edge at which the output data transitions. See Output Edge Synchronization for more information. If this pin is floating, the output clock (DCLK) is a DDR (Double Data Rate) clock (see Double Data Rate) and the output edge synchronization is irrelevant since data is clocked out on both DCLK edges.

Pin 127, if it is high or low in the non-extended control mode, sets the calibration delay. If pin 127 is floating, the calibration delay is the same as it would be with this pin low and the converter performs dual edge sampling (DES).

Table 13. Extended Control Mode Operation (Pin 14 Floating)

Pin	Function	
3	SCLK (Serial Clock)	
4	SDATA (Serial Data)	
127	SCS (Serial Interface Chip Select)	

#### **COMMON APPLICATION PITFALLS**

**Driving the inputs (analog or digital) beyond the power supply rails.** For device reliability, no input should go more than 150 mV below the ground pins or 150 mV above the supply pins. Exceeding these limits on even a transient basis may not only cause faulty or erratic operation, but may impair device reliability. It is not uncommon for high speed digital circuits to exhibit undershoot that goes more than a volt below ground. Controlling the impedance of high speed lines and terminating these lines in their characteristic impedance should control overshoot.

Care should be taken not to overdrive the inputs of the ADC08D1000. Such practice may lead to conversion inaccuracies and even to device damage.

Incorrect analog input common mode voltage in the d.c. coupled mode. As discussed in The Analog Inputs and THE ANALOG INPUT, the Input common mode voltage must remain within 50 mV of the  $V_{CMO}$  output , which has a variability with temperature that must also be tracked. Distortion performance will be degraded if the input common mode voltage is more than 50 mV from  $V_{CMO}$ .

**Using an inadequate amplifier to drive the analog input.** Use care when choosing a high frequency amplifier to drive the ADC08D1000 as many high speed amplifiers will have higher distortion than will the ADC08D1000, resulting in overall system performance degradation.

**Driving the V<sub>BG</sub> pin to change the reference voltage.** As mentioned in THE REFERENCE VOLTAGE, the reference voltage is intended to be fixed to provide one of two different full-scale values (650 mV<sub>P-P</sub> and 870 mV<sub>P-P</sub>). Over driving this pin will not change the full scale value, but can be used to change the LVDS common mode voltage from 0.8V to 1.2V by tying the  $V_{BG}$  pin to  $V_{A}$ .

**Driving the clock input with an excessively high level signal.** The ADC input clock level should not exceed the level described in the Operating Ratings Table or the input offset could change.

**Inadequate input clock levels.** As described in THE CLOCK INPUTS, insufficient input clock levels can result in poor performance. Excessive input clock levels could result in the introduction of an input offset.

Using a clock source with excessive jitter, using an excessively long input clock signal trace, or having other signals coupled to the input clock signal trace. This will cause the sampling interval to vary, causing excessive output noise and a reduction in SNR performance.


**Failure to provide adequate heat removal.** As described in Thermal Management, it is important to provide adequate heat removal to ensure device reliability. This can either be done with adequate air flow or the use of a simple heat sink built into the board. The backside pad should be grounded for best performance.

Table 14. Revision History

Date Released	Revision	Section	Changes
01/29/07	А	New Product/ Data Sheet Initial Release	New Product/ Data Sheet Initial Release, Revision A

Submit Documentation Feedback

NSTRUMENTS



# **Table 14. Revision History (continued)**

Date Released	Revision	Section	Changes
05/07/07	В	General Description, Features, Key Specifications, Ordering Information Table, Absolute Maximum Ratings, Typical Electrical Characteristics, Functional Description, Note	Last line in first paragraph. Added reference to Radiation to first three sections. Deleted Power Dissipation. Changed Conditions and Typical limits under Analog Output, Temperature Diode Characteristics & Digital Output Characteristics. Paragraph 1.1.6, Note 14 - (Vos) by 400mv to (Vos) by 330mv. Revision A will be archived.
05/28/09	С	Absolute Maximum Ratings, Operating Ratings	Absolute Maximum Ratings added Voltage on $V_{IN}^+$ , $V_{IN}^-$ . Operating Ratings changed $V_{IN}^+$ , $V_{IN}^-$ Voltage Range. Revision B will be Archived.
11/09/09	D	REGISTER DESCRIPTION (I-Channel Full- Scale Voltage Adjust and Q-Channel Full- Scale Voltage Adjust)	I-Channel Full-Scale Voltage Adjust and Q-Channel Full-Scale Voltage Adjust Bit 15:7 correction to binary values From 0110 0000 to 00100 000 Revision C will be archived.

Submit Documentation Feedback

49

#### IMPORTANT NOTICE

Texas Instruments Incorporated and its subsidiaries (TI) reserve the right to make corrections, enhancements, improvements and other changes to its semiconductor products and services per JESD46, latest issue, and to discontinue any product or service per JESD48, latest issue. Buyers should obtain the latest relevant information before placing orders and should verify that such information is current and complete. All semiconductor products (also referred to herein as "components") are sold subject to TI's terms and conditions of sale supplied at the time of order acknowledgment.

TI warrants performance of its components to the specifications applicable at the time of sale, in accordance with the warranty in TI's terms and conditions of sale of semiconductor products. Testing and other quality control techniques are used to the extent TI deems necessary to support this warranty. Except where mandated by applicable law, testing of all parameters of each component is not necessarily performed.

TI assumes no liability for applications assistance or the design of Buyers' products. Buyers are responsible for their products and applications using TI components. To minimize the risks associated with Buyers' products and applications, Buyers should provide adequate design and operating safeguards.

TI does not warrant or represent that any license, either express or implied, is granted under any patent right, copyright, mask work right, or other intellectual property right relating to any combination, machine, or process in which TI components or services are used. Information published by TI regarding third-party products or services does not constitute a license to use such products or services or a warranty or endorsement thereof. Use of such information may require a license from a third party under the patents or other intellectual property of the third party, or a license from TI under the patents or other intellectual property of TI.

Reproduction of significant portions of TI information in TI data books or data sheets is permissible only if reproduction is without alteration and is accompanied by all associated warranties, conditions, limitations, and notices. TI is not responsible or liable for such altered documentation. Information of third parties may be subject to additional restrictions.

Resale of TI components or services with statements different from or beyond the parameters stated by TI for that component or service voids all express and any implied warranties for the associated TI component or service and is an unfair and deceptive business practice. TI is not responsible or liable for any such statements.

Buyer acknowledges and agrees that it is solely responsible for compliance with all legal, regulatory and safety-related requirements concerning its products, and any use of TI components in its applications, notwithstanding any applications-related information or support that may be provided by TI. Buyer represents and agrees that it has all the necessary expertise to create and implement safeguards which anticipate dangerous consequences of failures, monitor failures and their consequences, lessen the likelihood of failures that might cause harm and take appropriate remedial actions. Buyer will fully indemnify TI and its representatives against any damages arising out of the use of any TI components in safety-critical applications.

In some cases, TI components may be promoted specifically to facilitate safety-related applications. With such components, TI's goal is to help enable customers to design and create their own end-product solutions that meet applicable functional safety standards and requirements. Nonetheless, such components are subject to these terms.

No TI components are authorized for use in FDA Class III (or similar life-critical medical equipment) unless authorized officers of the parties have executed a special agreement specifically governing such use.

Only those TI components which TI has specifically designated as military grade or "enhanced plastic" are designed and intended for use in military/aerospace applications or environments. Buyer acknowledges and agrees that any military or aerospace use of TI components which have *not* been so designated is solely at the Buyer's risk, and that Buyer is solely responsible for compliance with all legal and regulatory requirements in connection with such use.

TI has specifically designated certain components as meeting ISO/TS16949 requirements, mainly for automotive use. In any case of use of non-designated products, TI will not be responsible for any failure to meet ISO/TS16949.

Products Applications

Audio www.ti.com/audio Automotive and Transportation www.ti.com/automotive Communications and Telecom **Amplifiers** amplifier.ti.com www.ti.com/communications **Data Converters** dataconverter.ti.com Computers and Peripherals www.ti.com/computers **DLP® Products** www.dlp.com Consumer Electronics www.ti.com/consumer-apps

DSP **Energy and Lighting** dsp.ti.com www.ti.com/energy Clocks and Timers www.ti.com/clocks Industrial www.ti.com/industrial Interface interface.ti.com Medical www.ti.com/medical logic.ti.com Logic Security www.ti.com/security

Power Mgmt power.ti.com Space, Avionics and Defense www.ti.com/space-avionics-defense

Microcontrollers <u>microcontroller.ti.com</u> Video and Imaging <u>www.ti.com/video</u>

RFID www.ti-rfid.com

OMAP Applications Processors <a href="www.ti.com/omap">www.ti.com/omap</a> TI E2E Community <a href="e2e.ti.com">e2e.ti.com</a>

Wireless Connectivity <u>www.ti.com/wirelessconnectivity</u>